Journal Pre-proof

Rapid flood risk assessment of informal urban settlements in Maputo, Mozambique:
The case of Maxaquene A

Dua Zehra, Sandile Mbatha, Luiza C. Campos, Antonio Queface, Antonio Beleza,
Clemence Cavoli, Kamalasudhan Achuthan, Priti Parikh

PII: S2212-4209(19)30109-8

DOI: <https://doi.org/10.1016/j.ijdr.2019.101270>

Reference: IJDRR 101270

To appear in: *International Journal of Disaster Risk Reduction*

Received Date: 25 January 2019

Revised Date: 5 August 2019

Accepted Date: 6 August 2019

Please cite this article as: D. Zehra, S. Mbatha, L.C. Campos, A. Queface, A. Beleza, C. Cavoli, K. Achuthan, P. Parikh, Rapid flood risk assessment of informal urban settlements in Maputo, Mozambique: The case of Maxaquene A, *International Journal of Disaster Risk Reduction* (2019), doi: <https://doi.org/10.1016/j.ijdr.2019.101270>.

This is a PDF file of an article that has undergone enhancements after acceptance, such as the addition of a cover page and metadata, and formatting for readability, but it is not yet the definitive version of record. This version will undergo additional copyediting, typesetting and review before it is published in its final form, but we are providing this version to give early visibility of the article. Please note that, during the production process, errors may be discovered which could affect the content, and all legal disclaimers that apply to the journal pertain.

© 2019 Published by Elsevier Ltd.

Rapid Flood Risk Assessment of Informal Urban Settlements in Maputo, Mozambique: The Case of Maxaquene A

Dua Zehra, Sandile Mbatha, Luiza C. Campos, Antonio Queface, Antonio Beleza, Clemence Cavoli, Kamalasudhan Achuthan, *Priti Parikh

Ms Dua Zehra

Civil, Environmental and Geomatic Engineering Department
University College London, Chadwick Building
London, WC1E6BT.
Email: dua.zehra.15@alumni.ucl.ac.uk

Dr. Sandile Mbatha

Faculty of Architecture and Planning,
University of Stuttgart, Germany
Email: sandile.mbatha@gmail.com

Dr. Luiza C. Campos

Civil, Environmental and Geomatic Engineering Department
University College London. Chadwick Building
London WC1E6BT.
Email: luiza.campos@ucl.ac.uk

Professor Antonio Queface

Eduardo Mondlane University,
Maputo, Mozambique.
Email: antonio.queface@gmail.com

Mr. Antonio Beleza

National Institute for Disaster Management,
Maputo, Mozambique.
Email: antonio.beleza@gmail.com

Dr. Clemence Cavoli

Civil, Environmental and Geomatic Engineering Department
University College London. Chadwick Building
London WC1E6BT.
Email: clemence.cavoli@ucl.ac.uk

Dr. Kamalasudhan Achuthan

Civil, Environmental and Geomatic Engineering Department
University College London. Chadwick Building
London WC1E6BT.
Email: k.achuthan@ucl.ac.uk

***Dr. Priti Parikh (Corresponding author)**

Civil, Environmental and Geomatic Engineering Department
University College London. Chadwick Building
London WC1E6BT.
Email: priti.parikh@ucl.ac.uk

Rapid Flood Risk Assessment of Informal Urban Settlements in Maputo, Mozambique: The Case of Maxaquene A

Abstract

Cities across the Global South are facing huge challenges associated with rapid urbanisation, lack of infrastructure services and climate change, including frequent storms and recurrent floods that inundate large areas of their urban landscape. Often, the worst affected groups are those living in low-income settlements located in floodplains of the city. Maxaquene A is an example of such a settlement in Maputo, Mozambique, a country with a strong history of storms and floods due to its geographical location. This paper describes a rapid flood risk assessment conducted by the authors, in Maxaquene A. The assessment obtained both community and external stakeholder perceptions of challenges in the neighbourhood, accompanied by a description of how floods have affected infrastructure such as drainage and sanitation, services such as pit emptying and solid waste collection, and localised infrastructure solutions developed by the community as a coping mechanism. The assessment highlighted the need for collaboration with community members to co-develop appropriate flood risk management strategies and infrastructure solutions. This work will pave the way for greater in-depth research with residents of Maxaquene A, neighbouring settlements in Maputo and other informal settlements in the Global South, to drive change in climate change adaptation across the built environment.

Keywords

Flooding, risk, drainage, sanitation, solid waste, climate change, informal settlement, Maputo

Introduction

Urbanisation coupled with climate change pose a challenge for well-being of citizens in future cities (Jha et al., 2012). Rapid urbanisation and poor planning processes have resulted in haphazard growth of slums and blockage of natural drainage paths in the cities such as Maputo, causing an exacerbation of flood events. Recurrent floods including the recent Cyclone Idai in Maputo have had a negative impact on infrastructure services such as sanitation, solid waste management, water supply, housing and accessibility for emergency response; which is why assessment techniques with low resourcing requirements are needed. In the longer term, there is a need to incorporate flood risk management in formal planning processes and in the short term, there is a need for rapid assessments, which can identify areas of high risk in cities in order to aid adaptation, risk preparedness and detailed assessments using mixed methods. Assessment techniques with low resourcing requirements are cost effective and can be used frequently both post flooding and as a tool to aid adaptation and risk preparedness.

Informal settlements are typically characterised with poor environmental conditions, dilapidated housing and lack of access to basic infrastructure services such as water, sanitation, energy, access roads and drainage systems.

In Sub-Saharan Africa (SSA) 59% of the urban population currently resides in slums, and it is estimated that 1.2 billion residents in SSA will be slum dwellers by 2050 (UN-Habitat, 2016). This has resulted in gaps in basic infrastructure services, as most cities do not have uniform access to water and sanitation services, with further limited access to reliable services in particular. It is likely that climate change and associated flood events will have a negative impact on the limited infrastructure that exists and will also act as a barrier for future investment in infrastructure, due to the limited resources available for city governments. Very often these informal settlements are located in flood risk zones near natural drainage paths and riverine, thereby bearing the brunt of flooding. The sub-standard housing and infrastructure conditions further deteriorate during flooding and pose challenges for residents who are often subject to repeated occurrences of such events. The provision of infrastructure in informal settlements has the potential to improve quality of life (Parikh, Parikh & McRobie, 2012). Hence, there is a need to focus on improved provision and planning for infrastructure services as part of climate change adaptation plans for future cities. Between 1980 and 2009 there were an estimated 540,000 deaths and 2.8 billion people affected by floods (Doocy et al., 2013). Urbanisation combined with haphazard development, poor planning, high density, concentration of poor and marginalised populations and lack of

opportunity for community members to actively shape adaptation planning. Despite the well documented knowledge of informal settlements as most vulnerable to flooding, they are, more often than not, excluded from most formal planning and adaptation processes. In response, Jha, Bloch & Lamond (2012) have highlighted the need for participatory integrated urban flood risk management strategies to ensure that all stakeholders can provide inputs into both hard measures such as defence barriers and infrastructure services, and soft measures such as improved evacuation plans. Community participation is a critical process in facilitating localised resilience and social capital necessary for building behavioural change critical in supporting climate change adaptation interventions (Kwadijk, 2010).

Figure 1. Map of Mozambique, Maputo City, Maxaquene A

Mozambique has a strong history of torrential rainfall and tropical cyclones resulting in frequent flooding. It is a 'downstream' country, which must manage water flow from nine major river systems that intersect it to drain into the Indian Ocean, requiring the country to manage impacts of rainfall that fall far beyond its own catchment area (Fairhurst, Rowswell and Nhleko, 2011). Since 1970, Mozambique has been hit by over 35 significant cyclones and five major flood events (2000, 2001, 2007, 2008) (UN-Habitat, 2010) and most recent event in 2019. With a climate already so susceptible to natural disaster, the rise in urban population across its cities, has left damaging consequences for the country's built environment, and social and economic development (Fairhurst et al., 2011).

Maputo covers an area of 300 km², with a population of approximately 1.3 million (UN-Habitat, 2010). It is positioned on the coastal plain and it lies at the confluence of three major rivers: Maputo, Umbeluzi and Incomati (ICLEI, 2011). The location of Maputo combined with torrential rains associated with cyclones and intense short rains aggravates the flooding challenges. Floods such as the 2000 flood episode, was an outcome of the combination of runoff floods from catchment

areas in the north of the country and localised flooding from torrential rains. Climate change has affected 720,000 people and has put at risk 7% of the city's asset with informal settlements and economic hubs (ports and coastal real estate) affected the most due to recent flooding events (Logchem, and Queface, 2012, Matoso, 2015).

Urban settlements such as Maxaquene A have been unable to cope with flooding as frequent rainfalls disrupt life in a setting with poor infrastructure services with limited response from the local municipality due to the high frequency of flooding events. Through a rapid assessment of flooding risk and damage to infrastructure facilities this study examines how flooding affects day-to-day life of residents of Maxaquene A. The objective of the study was to identify and understand the nature of localised community driven responses to pre and post flooding events to assess perceived infrastructural challenges and understand localised solutions developed by the community. This would help to evaluate how storm water drainage, road conditions, solid waste management, building conditions and emergency services impact on the everyday lives of residents in Maxaquene A.

Participatory approaches in disaster risk management

With high rates of significant flood events coupled with a high proportion of population residing in informal

that residents first try to move their belongings to higher grounds and evacuation is seen as a last resort (Artur and Hilhorst, 2012).

Studies of urban flooding cases have been carried out for numerous cities globally (Noosorn and Niamkamnerd, 2009; Kita, 2017; Castan Broto, Boyd and Ensor, 2015). Padawangi et al. (2016) describe a participatory mapping technique that made use of geo-tagged Twitter posts to enable web-based flood mapping in a specific Jakarta settlement. Mulligan et al. (2016) and Royo et al. (2018) build a case for community-responsive adaptation to urban flooding in informal settlements and use mixed methods to assess infrastructure needs for residents in Kibera settlement in Nairobi, Kenya. Few (2003) highlights that intervention efforts designed to build up the assets of the poor to withstand shocks will be increasingly important in reducing the human burden from flooding. Most climate change adaptation programmes depends on individual households and local managers of natural resources where communities adapt over a period of time as noted in Mozambique (Artur and Hilhorst, 2012). In order to sufficiently support local action it is imperative to build an understanding of the urban poor's practices and responses and the context under which their responses occur. Fitchett (2013) proposes adaptative co-management as a means of including and elevating the value of local knowledge systems and social structures to enable policymakers and professionals learn about environmental practices and urban dynamics.

Specifically to the setting of informal settlements in Mozambique, Kayaga et al. (2015) assessed sanitation needs in three settlements – Chamanculo B, Maxaquene A and Urbanizacao using a combination of semi-structured interviews with stakeholders, observational analysis and review of secondary data. Campos et al. (2015) conducted a rapid participatory risk assessment methodology for sanitation systems in Maxaquene A and Chamanculo D where they develop a list of risk indicators for community risk assessment in informal settlements. The risks were assessed through a combination of participatory techniques such as household interviews, workshops and group discussions within the communities. These projects provided an opportunity for local communities to identify their needs and express priorities to the municipality. The common factor across both those projects was the use of multitude of participatory techniques for the purposes of triangulation to validate findings and ensure that the community consultation was not influenced by few key/strong stakeholders and was therefore more inclusive.

Castán Broto, Oballa, and Junior (2013) analyse the role of Governance in climate change vulnerability and explore urban interventions emerging from beyond the local Government in Mozambique. ActionAid International (2006) explores the relationship between climate change, flooding and Maputo as a reflection of their impact on the Global South. UN-Habitat compiled a city climate change assessment for Maputo (UN-Habitat, 2010) that took hazards like floods, droughts and rising sea levels into account. While organisations like UN-Habitat and ActionAid have provided brief and concise city profiles for Maputo and Maxaquene on the impacts of climate change, projects and interventions have seemed to focus an element of infrastructure whether it may be sanitation (Campos et al., 2015; Kayaga et al., 2015), storm water drainage (Palalane, 2010) or solid waste management (Kruks-Wisner, 2006). This study will build on previous assessments, in particular Campos et al, 2015 and Kayaga et al, 2015, to develop a rapid assessment which is holistic and integrates multiple infrastructure services in lieu of a sectoral approach.

Case Study

Mozambique's post-independence period saw an influx of migrant workers resulting in unplanned expansion with limited provision of infrastructure services. Maputo housed 45% of the total urban population in Mozambique, 70% of which were considered to be living below the poverty line (UN-Habitat, 2010). The recent census does not specifically include statistics on slum population in Maputo as most residents do not consider themselves to be informal settlement (slum) residents. Residents have a right to reside and eviction is challenging to achieve once they occupy land for more than two years. Many informal settlements around Maputo were built in unsuitable land such as flood plains, with the expansion taking place rapidly into low-lying and marshy areas with a high flood risk. This has led to much higher vulnerability to flooding, as the rise in urban activity has increased the run-off of rainwater to rivers (Fairhurst et al. 2011).

Figure 2. Map of Maputo City and its main roads. Maxaquene A is labelled in yellow. (Bradford and Puri 2015)

Maxaquene A is part of the larger KaMaxaquene District. It is one of the oldest settlements of the city with the inhabitants predominantly migrants who had come to Maputo to seek employment during colonial era. Maxaquene A was formed as a response to rapid urbanisation as an organic extension of the formal settlement of Mafalala. It has established leadership hierarchies that influence social dynamics and guide the process of engagement with the state. Subdivisions of the community are informal but they consist of locally recognised leadership hierarchies legitimated by the local state and other organs of the state which engage with the community on various issues pertaining through those structures and hierarchies. At a spatial level, the quarters of Maxaquene A adjacent to Mafalala follow a cadastral structure with an orderly pattern. However, as the settlement grew organically and population densities increased over the years, this structure disappeared. The neighbourhood is now divided into 60 blocks or quarters, each comprising of 10 to 35 homes. Each quarter comes under the jurisdiction of one chief of quarter, who acts as a key community leader and reports to the Maxaquene neighbourhood secretary. Due to its favourable location in the city for livelihood opportunities, Maxaquene has grown to house 25000 inhabitants (Kayaga et al. 2015) with limited infrastructure services and high levels of vulnerability to flooding demonstrating the failure of urban planning processes.

Flooding in Mozambique is managed at the national level by the Instituto Nacional de Gestão de Calamidades (National Institute for Disaster Management) (INGC), which contributes to national policy development and plays a coordinating role for emergency response by having direct engagement with low income urban settlements in the country. Originally created in the 1980s to deal with response to Mozambique's civil war, it changed its focus to disaster prevention, preparedness, early recovery and reconstruction after the 2000 floods (UNECA, 2015). In 2006, the INGC had established a Master Plan for Prevention and Mitigation of Natural Disasters. Recently, a new Master Plan for Disaster Risk Reduction (2017 – 2030) highlighting disaster prevention at national, provincial, district and community levels replaced the previous Master. INGC implemented a comprehensive situation analysis using a Systematic Inventory and Evaluation for Risk Assessment (SIERA) methodology jointly with UNDP (2010) in order to improve preparedness for natural disasters. The UNECA (2015) assessment on Disaster Risk Reduction (DRR) strategies in Mozambique have been positive about INGC's efforts to date, with recommendations on improvement around community-based

communities through the Comites Locais de Gestao do Risco de Calamidades (Local Committee for Disaster Risk Management) (CLGRC). Through CLGRC, INGC invite local community members to get involved and be trained, equipped and informed about disasters and risk management. The committee must have 18 members who can participate on a voluntary basis. Annual refresher trainings are held just before the start of the rainy season. The INGC representative participating in stakeholder interviews reports that the CLGRC has been functioning effectively since its inception though challenges on retaining members has been noted due to the voluntary nature of involvement (Matoso, 2015). A few weeks before the rainy season, the INGC and the municipality conduct flood risk awareness campaigns in the region. Flood warnings are issued 24 hours in advance through the CLGRC to alert the local community. Small access roads and pathways are used as evacuation routes by the evacuation authority and the City Council then provides shuttle buses for evacuation out of the area. Return to homes from the evacuation sites depends on levels of flood severity, and the CLGRC carries out an assessment of the neighbourhood and inform the residents whether it is safe to return to their homes. Sometimes, people choose to do their own assessment of conditions and decide when to return. So far 34 committees have been formed but currently only the ones in high risk areas including Maxaquene are operational (Matoso, 2015)

Methodology

Fieldwork was conducted in March 2016 for two weeks to coincide with Mozambique's wet season in Maxaquene A by the second and fifth author building on the extensive knowledge and inexperience of in-country author's. Prior to this the authors conducted a desk-based literature review to identify key stakeholders engaged with flood adaptation work in Maputo and understand the general context in Maputo. The data collection process was designed to respond to local contexts and realities with qualitative techniques. The ambition of the project was to gain an understanding of the neighbourhood from three different dimensions: the external view of the neighbourhood through our desk-based research, literature reviews and observations in the field; the lived experiences of locals living in the settlement itself; and the external partners that have and/or continue to work on flood risk management with the settlement (See Table 1).

Stage	Description
1. Desk-based research	Literature review
2. Fieldwork with community in Maxaquene A	Discussions with chiefs of quarters 4 and 35 to identify flood risk areas
	Transect walks in flood prone quarters 15, 17, 21, 35, 41 and 57 to 60
	Community workshop to include focus group discussion and mapping exercise conducted with 35 respondents from the flood prone quarters
3. Fieldwork with external stakeholders in Maputo	Semi-structured interviews with seven external stakeholders of Maxaquene A

Table 1. List of stages of research and fieldwork in the project.

A combination of participatory tools such as stakeholder interviews, transect walks with local chiefs, workshops to include group discussions and mapping was used to collect data. In the workshop, key topics covered included general perceptions on flooding, perceived impact on infrastructure services, evacuation processes and a mapping exercise where key features such as flood prone sections were identified. These ideas emerge from approaches such as Rapid Rural Appraisal (RRA) and Participatory Rural Appraisal (PRA) which facilitates a quicker and more cost-effective approach to community engagement and enables researchers to gain contextual information and insights from local communities (Chambers, 1994). This work also builds the work of Campos et al. (2015) and Kayaga et al. (2015) by further strengthening the participatory tools and also including an assessment on storm water drainage, road conditions, solid waste management, building conditions and emergency response.

Figure 3. Mapping produced by participants during the community workshop in Maxaquene A.

responses to flooding in the community. These were noted during the workshop as the elders led the discussions on flooding matters on behalf of the community. The local government stakeholders also seemed to accept and legitimate their representation of community matters. Discussions were arranged with the elders of the community at the Maxaquene A district office, including chief of quarters 35 and 4. The chief of quarter 35 who had lived in Maxaquene A since the 1960s identified the quarters that were most vulnerable to flooding, including those located at the bottom of settlement slopes: quarters 15, 17, 21, 35, 41 and 57 to 60 based on his personal observations. After this, transect walks were conducted through the neighbourhood with the aim of making observations and collecting photographic evidence of key infrastructure, community resources, drainage, and household and community responses to flooding. During the transect walk, community members also confirmed the quarters identified by the chief of quarter 35 as the worst hit by floods. Hence, those quarters were selected as the focus for an in-depth community workshop with two components: focus group discussion and mapping exercise (Figure 3).

The objective of the community workshop was to assess general perceptions and concerns about the impacts of flooding in Maxaquene A and to understand their day-to-day responses to flooding risk. A representative sample of residents from quarters 15, 17, 21, 35, 41 and 57 to 60 participated in the workshop and were joined by leaders of each quarter. Thirty-five participants (15 men and 20 women) shared their past and current experiences of flooding and impact of flooding on their infrastructure such as housing, toilets, pathways and roads. The workshop commenced with a mapping exercise where the participants identified areas of high risk and worst affected roads and quarters. Through a semi-structured format¹, the discussion then highlighted specific challenges in related to evacuation, physical infrastructure (solid waste management, sanitation, roads, storm water drains) and flood risk management plans. During the workshop, it was noted that residents had an in-depth knowledge of their settlement and flooding conditions dating as far back as the 1970s.

In addition, seven external stakeholders who have previously worked in Maxaquene A were interviewed in order to assess their perceptions of challenges posed by flooding and this evidence was used in the qualitative analysis to triangulate findings from the community workshop. Stakeholders included civil society organisations, academics, practitioners and Government officials (Table 2). The interviews were crucial in gaining an external perspective of flood risk in the area, and level of interventions by organisations. Each participant explained how their organisation engaged with residents, defined key challenges that Maxaquene A currently faces and how these challenges have or will pose threats to future development interventions.

Stakeholder	Stakeholder Group
1 Department of Architecture and City Planning, Eduardo Mondlane University, Maputo	Higher Education
2 Risk Reduction Programme Officer, United Nations Development Programme (UNDP)	Multi-lateral development agency
3 Climate Change and Environment Programme Officer, UNDP	Multi-lateral development agency
4 Representative, National Institute of Disaster	Ministry of Foreign Affairs and Cooperation

6	Metro Police Officer, Maputo City Council	Local government
7	Officer, UN-HABITAT Maputo	Multi-lateral Development Agency

Results and Discussion

Perceived Impact of Flooding on Infrastructure

Residents highlighted that the 1972 flooding impact had not been as severe because the region's soil had a high infiltration capacity to drain the water naturally. It is important to note that densities were much lower at the time (Kayaga et al., 2015). Over time however, the situation has progressively worsened with the water table rising and increasing the overall flood vulnerability of the settlement. During the 2000 floods residents have noted that floodwater remained stagnant for many days, sometimes taking up to 3 months to drain after heavy rainfall. Main causes of flooding were perceived to be the diminishing infiltration capacity of the soil, lack of urban planning and the absence of a functioning drainage system. The section below describes infrastructural challenges faced by the residents in Maxaquene A:

i. Road Network Hierarchy

A structural hierarchy of roads was found in and around Maxaquene A with the largest roads across the city as main highways, which are formally constructed and tarred, and help to connect strategic parts of the city like the airport and Central Business District. They also serve as main connections between the city and other regions of Mozambique. Avenida Acordos de Lusaka, Avenida Joaquim Chissano and Avenida das Forças Populares de Liberação de Moçambique are three highways that border the Maxaquene A settlement. The second structure in the hierarchy are connector roads like Avenida Do Zimbabwe and Avenida De Moçambique which have also been formally constructed by city and link parts of the city to the main highways. Once inside the settlements however, a network of unpaved access roads and pathways was established to divide the neighbourhood into quarters. Although these access roads and pathways have grown organically in response to mobility needs through the area with vehicles, the quarters are formally recognised by the municipality. Further access to the quarters is through narrow pathways or unpaved alleys that enable locals to reach their homes on foot. This hierarchy is crucial in understanding the impact of torrential rainfall on Maxaquene A and how this structure affects drainage and evacuation out of the neighbourhood. The community recognises that all roads are affected by flooding because settlement drainage systems remain dysfunctional, but the poor condition of access roads and pathways exacerbates impact within the settlement. Floodwater can gather in large puddles and make transit much more difficult for Maxaquene A's residents. Access to quarters is blocked due to water logging in the narrow pathways.

ii. Stormwater Drainage

Urban informal settlements are more vulnerable to flooding due to high population densities and limited coverage of drainage infrastructure (Grahn and Nyberg 2017). Stormwater drainage in Maxaquene A remains poorly functioning and does not have the capacity to serve all roads and pathways in the neighbourhood. In Maxaquene A, storm water drains were constructed along some (though not all) of its connector and access roads by Maputo City Council in the 1980s. ESF (Enginyeria Sense Fronteres) constructed drainage channels in the neighbourhood between 2007 and 2010. The work conducted by the two institutions varied greatly in both design and execution. The residents claimed that drainage channels implemented by ESF seemed to function better as compared to the ones built by the city. These claims were confirmed during the fieldwork and through observation.

According to local NGOs and municipal representatives working in the area the City Council built channels without community consultation or participation. They claim that most of the local residents in fact opposed it, highlighting that they were dangerous for the community. Their 1.5-metre wide and 1.5-metre deep channel structure are usually prone to blockage as residents dump MSW into channels and cause mosquitoes to accumulate, triggering the spread of malaria. Poor design consideration is also highlighted by the fact that water supply pipes intersect these channels. It was observed that that some of these pipes had burst and there was a danger of water contamination, a hazard recognised by locals as well. The risk of children falling into the drains is even greater in channels as wide as 3 metres, found on settlement connector roads (Figure 4). There is a

resilience and develop local skills so that in the long-term, residents could operate and maintain the channels on a regular basis. Alongside the ESF teams, the residents built these new drainage channels in Maxaquene A and acquired the skills to assist other communities in implementing the drainage channels or gain employment in their design and maintenance. In comparison to Council-built trenches, the ESF design was much smaller – 60cm wide and 60cm deep – with a steep gradient to allow water to flow out of the area. Their small size minimised any potential danger of children falling in and allowed them to be built alongside more roads in the settlement because they did not encroach into public space (Figure 5). In 2012, community members stated that the city authorities destroyed many ESF-built drainage channels to make way for the industrial size Council structures. This is reported to have been done without consulting partners working in the settlement or the community. The municipality claimed that implementing an effective drainage system was made difficult by the lack of approved town planning scheme and was exacerbated by high densities and unplanned informal patterns of the settlement. After this, ESF stopped the construction of new channels in Maxaquene A and instead focused projects on operation and maintenance of existing trenches and other service.

Figure 4. A 3-metre wide open drainage channel in Maxaquene A

Figure 5. ESF-built channels along an access road in Maxaquene A. Their size was much smaller and allowed safe crossing into properties.

iii. Solid Waste Management

Solid Waste Management (SWM) is also Maxaquene A's pressing challenge, with the entire neighbourhood affected by waste dumped locally. The extent of SWM can be observed throughout the neighbourhood where roads, pathways and water channels are blocked by waste from households. Waste is also dumped inside old, abandoned and dilapidated buildings in the neighbourhood. The local community recognised this as a severe issue and highlighted the lack of infrastructure provision such as municipal bins and collection services as the main cause for this problem, as well as lack of awareness amongst residents regarding SWM best practice. The high density, narrow routes and poor road conditions in the settlement made waste collection difficult. There are mobile waste collectors who use wheelbarrows to collect the municipal solid waste (MSW). While this informal system works to reduce quantities in the area, they are unable to reach all alleys and narrow pathways in the settlement and are also faced with the inconvenience of residents not putting household waste into plastic bags. Residents felt that although the municipality criticised their inability to adequately contain the waste, they had not provided suitable SWM services in response. They recognised that the impact of recurrent flooding was exacerbated by MSW in the area, particularly because it blocked open drainage channels (Figure 7). The transect walk through Maxaquene A showed waste being collected by mobile collectors into skips and burnt in large quantities (Figure 8); demonstrating gaps in addressing public health and the subsequent environmental impacts relating to waste within the community.

Figure 7. Waste clogging an open drainage channel

Figure 8. Collected waste being burnt in a community skip.

iv. Effect on Homes and Livelihoods

After heavy rainfall residents describe how water inundates homes, sometime reaching heights of over two metres. As a result, house foundations have weakened and many homes are now at risk of collapsing. Since the 2000 floods, most properties in the settlement were observed to have mould inside due to inability to dry completely and has led to implications on public health (Azuma et al. 2014). To try and protect their homes from collapsing, residents have been forced to re-plaster their properties on frequent basis. Many homes have collapsed due to flooding in the past and have had to be rebuilt. The community indicated that the Government is not involved in the rebuilding process and households are responsible for rebuilding their homes. The organic and haphazard growth of the settlement has led community members to build their homes on any available land over the decades, causing natural waterways to become disrupted and impeding the flow of storm water out of the area. The community members held several meetings with the City Council to discuss land use planning but this had not yielded any results. The municipal representative interviewed during fieldwork explained that this was due largely to a lack of funding. Residents have changed their choice of building materials and techniques by investing more in concrete floors and strengthening walls with waterproofing.

It was observed that responses to flooding from the community in Maxaquene A were more passive than active. There appears to be focus on improving infrastructure to avoid floodwater entering houses. For example,

from roads and pathways into the school grounds (Figure 11). Residents perceived the school walls as an obstacle for water flowing out of the settlement.

Figure 9. Concrete pathway built along a narrow pathway to avoid floodwater

Figure 10. Protective brick wall built in front of a property to keep floodwater out of the home.

Figure 11. Holes dug out of local school walls to drain water

The workshops highlighted how floods had severely affected economic activity in the neighbourhood of Maxaquene A. For local businesses, the challenge was two-fold: shop and stall owners struggled to reach their businesses after flooding and customers found it difficult to transit through flooded roads and pathways to make any purchase. This created a loss of income when considering the frequency of flooding and the fact that water was reported to remain in the neighbourhood for up to three months after heavy rainfall. Residents who travel out of the settlement for work explain that they could only stay a maximum of two days away from work as their employers 'do not want to hear excuses'. Residents could lose up to 100 Metical's (1.46 USD) per day of work missed. Hence, residents choose not to stay away from work at all due to a fear of losing their jobs. In order to transit through the neighbourhood on a daily basis, they wore gumboots across flooded roads and pathways until they are out of the settlement, and they then changed into normal shoes for work. Those without gumboots wore plastic bags on their feet as makeshift gumboots.

v. Sanitation

The most common form of sanitation in Maxaquene A is Ventilated Improved Pit Latrines (VIPs). Some have been constructed by ESF and WSUP in their latrine improvement and pit emptying pilot projects (WIN-SA 2012) while others have been built by residents. Some residents have converted their VIPs into flush toilets, and the pit which is used as a septic tank to collect discharged waste is separated from the toilet. In response to the flooding, the residents have commonly opted for elevated sanitation facilities and raised pits, as they are aware that the water level can rise. Residents of Maxaquene A have also reported that the water level in the pits can rise, and they have to use plastic bags to collect the waste. Some residents have also reported that the water level in the pits can rise, and they have to use plastic bags to collect the waste.

Emptying and maintenance of latrines remain a huge challenge in Maxaquene A due to inaccessibility issues that arise as the result of high densities in the settlement. The high-water table limits the pit depth of VIPs and requires them to be emptied more frequently. Often residents are restricted by high population density from constructing a second pit (Adeagbo et al., 2016). Some residents employ manual pit emptiers for their toilets but inaccessibility issues still exist in settlement quarters and employing external emptiers can prove very expensive for low-income residents. Residents estimate the emptying costs to be approximately 800 Meticals (11 US Dollars) per pit. To avoid such costs, some residents dump their faecal waste into channels in the middle of the night. The inaccessibility challenges in Maxaquene A resulted in the city being unable to send pit-emptying trucks for maintenance of sanitation infrastructure forcing residents to either employ external emptiers, empty pits themselves or dump waste into channels.

There is recognition that many challenges associated with flood risk are linked to problems surrounding sanitation, which in turn are caused by a lack of education and awareness amongst the residents about the correct disposal of faecal waste and its health implications (Campos et al., 2015). The lack of networked infrastructure also leaves a gap in faecal sludge transport and disposal services. The residents believe there is a level of neglect from the authorities, resulting in a lack of funding for the settlement's infrastructure. The residents believe that investment in infrastructure would drastically improve their situation. Residents shared that they were able to maintain sanitation systems themselves but required the City to install suitable infrastructure that would greatly assist them; for example, a faecal sludge collection service to transport it out of the neighbourhood or networked systems. The municipal representative interviewed indicated that the city has just recently approved a legal framework to regulate the construction and emptying of VIP latrines in Maputo. He also mentioned that there have also been proposals for a reticulated sanitation system in the region. At this stage however, it is unclear whether this will translate to installation of flush toilets in informal settlements.

Response to Flooding and Challenges in Maxaquene A

The findings of the research indicate significant challenges in disaster risk management in Maxaquene A. Residents note that the evacuation procedures were chaotic with limited information about place of evacuation, routes to places of safety and transport options. Residents also claimed that evacuation places were not conducive for families. In most situations they did not know whether to bring their personal belongings or leave them behind. The community saw the biggest challenge to evacuation as lack of access to adequate information and inadequate planning from the city authorities during floods.

Furthermore, residents complained about crime as a reason for not feeling comfortable evacuating during floods. They experienced theft after leaving their belongings behind during evacuation. As a result, many residents were reluctant to evacuate during floods because of fear of losing their assets. To mitigate this risk only children and young family members were allowed to evacuate during the 2000 floods while adults remained in homes to protect their belongings. Adults instead chose to use high tables to protect furniture from water and also as a place to sleep until the water subsided.

Communication gaps between INGC representatives and residents was noted especially around the implications of living in a floodplain. Relocation is a huge challenge due to conflicting views between authorities and residents on the subject; residents feel that if a person has been evacuated more than four times, the city should permanently relocate them because it indicates the area is unsafe. However, people are reluctant to relocate because they expect the city to compensate them for relocating. This reluctance is primarily because the city created a precedence by compensating relocations during the construction of the drainage systems. It is worth noting that despite accepting the relocation fee, many residents did not move out to allow for the project to be implemented mainly due to Maxaquene A's strategic proximity to work opportunities which other places may not offer. Residents' refusal to relocate has resulted in authorities now trying to upgrade existing infrastructure in the neighbourhood in a piecemeal approach in lieu of installing new systems.

A chief of quarters claimed that the Government did not intervene to help restore services or reduce flooding impact on businesses and loss of income. For basic services such as electricity, it took up to two weeks to restore to normal functionality. Overall, it was difficult to ascertain how long services took to be restored because it largely depended on flood severity and intervention. For example, residents indicated that there is a settlement road that was destroyed in the 2000 floods and had still not yet been rebuilt. Residents compared their neighbourhood to other settlements like Chamanculo which they felt had gained attention from the City

in some quarters. The ESF representative interviewed in the field explained that this was largely due to the lack of urban planning in the settlement that made it difficult for ESF to expand their project in the region. The external stakeholders interviewed (Table 3) highlighted key challenges for Maxaquene A in related to flooding.

Table 3. Key development challenges identified for Maxaquene A.

Issue	Observation	Suggested intervention
No Formal Urban Plan	The absence or lack of implementation of an urban plan coupled with sporadic and high rates of population growth in Maxaquene A made it difficult to support land use planning activities. Infrastructure development is difficult for the city authorities as the level of service provision, the number of connections and extension of services is continuously changing. The main reason for failure of ESF's work on open drainage channels in the settlement was the lack of an urban plan beyond quarters 57 to 60, leaving the remainder of the settlement without operational drainage channels. The map produced by ESF with the local community was useful in understanding the layout of the area at the time and helped in their project implementation.	Planning authorities at the national, provincial (Maputo Cidade) and local level, should ensure that (cross-sectorial) urban plans are adequately established and implemented. International organisations (such as the World Bank) should provide relevant technical and financial support to facilitate these processes. These plans need to address flooding, SWM and evacuation issues and need to be regularly updated to reflect demographic changes. Quantitative and qualitative data related to flooding and SWM should be collected on a regular basis to inform decision-making and planning.
Flooding Treated as a Normal Occurrence	Developing a culture of disaster management in Maxaquene A is difficult as flooding is seen to be a regular occurrence and residents choose to continue with their daily activities, despite any risks and hazards that arise. With flooding events traced back to the 1970s in the settlement, residents have grown accustomed to floodwaters. The community's response is more reactionary than proactive; no precautionary measures are taken to reduce the impact of flooding in the area, whether it be in infrastructure or social behaviour. Instead, areas of flooding are avoided until water subsides and it is hence difficult to put a disaster response or intervention in place.	International, national, provincial and local stakeholders (e.g. relevant government departments, NGOs, international donors) should focus on raising awareness (via radio, leaflets, billboards, etc.) amongst residents who live in affected areas. Awareness raising could focus on the risks associated with flooding, how local residents can contribute to preventing flooding issues (e.g. by not throwing rubbish in sewage to avoid blockages) and the appropriate disaster response, in particular evacuation plans for different neighbourhoods.
Reluctance to Relocate	Residents have resisted relocation from their homes for both emergency evacuation and development projects. This behaviour is linked to a fear of theft and land ownership related challenges. This poses a challenge for both disaster management and development of infrastructure in the region. The INGC representative revealed that when the City Council had planned to install a drainage system through the area, only 10 residents agreed to relocate for drainage construction to take place, putting an end to the project. Hence, the only option remaining is to upgrade existing	Consultation exercises could be run to design attractive compensation schemes for local communities to relocate.

	carried out in Maxaquene A, it is first crucial to improve solid waste management and sanitation facilities. It is clear that this has a negative impact on public health and the environment.	and fostering adequate behavioural change. In parallel, solid waste management and sanitation facilities could be put in place.
Poor Construction and Operation Techniques	Homes in Maxaquene A have been poorly constructed from low quality building materials which bear the burden of recurrent flooding. The damage caused by floods forced residents to repeatedly reinvest in their homes so that they remain intact. The 2014 Disaster Management Law prohibits building properties on vulnerable or disaster-prone areas, but since urbanisation has been taking place in Maputo since the 1970s this excludes existing informal settlements like Maxaquene A. Sanitation facilities like pit latrines overflow resulting in contamination in the surrounding areas during floods. The poorly constructed open channels exacerbate the problem of flooding, as water does not drained out of the area.	Regeneration schemes supported by public authorities and other relevant institutions (e.g. Engineers without borders) should focus on climate resilient housing and adequate and sustainable sanitation systems.

Conclusion

Key infrastructure challenges at community level included poor conditions of roads and drainage channels, limited drainage channels, absence of waste collection and disposal, resulting in blocked drains and narrow access routes. Public health and safety issues included poor sanitation and solid waste practices; poor drainage and contamination of water resulting in prevalence of malaria and diarrhoea in the neighbourhood. Flooding therefore has an impact on day-to-day lives of residents affecting mobility, health and well-being. Kemp et al (2011) note the need to invest in infrastructure as part of climate change adaptation plans as the lack of infrastructure has a direct impact on livelihoods.

The most urgent concerns of the neighbourhood are solid waste management and drainage infrastructure. The project shows that the challenge of solid waste management and adequate drainage go hand in hand; the lack of functioning channels in the area means storm water cannot be drained out of the area, and existing channels, due to the lack of solid waste collection services are being clogged by rubbish. Solid waste management systems can be improved by adding enough municipal bins on access and connector roads to keep channels free and make collection of waste from these sites more efficient than having to transit all roads of the neighbourhood. Construction techniques should be regulated for drainage channels to ensure safety for children and appropriate designs to ensure water is drained naturally out the settlement. For improved flood prevention, suitable drainage infrastructure and waste collection services that both cover the entire neighbourhood will help make a difference in the area as poor sanitation infrastructure aggravates public health risks.

The complex road network hierarchy of Maxaquene A is an obstacle for of these interventions, due to the organic nature of the area's growth in the past few decades. Concrete roads and storm drains need to follow the natural topography to reduce flooding. This would reduce the current investment into brick walls and concrete pathways that the residents currently fund through their own funds. With improved drainage facilities, one may find less inundation of homes and alleyways, reducing the level of damage caused to buildings and homes, and make it easier for residents to traverse the neighbourhood on a daily basis. Similarly, the issue of sanitation and pits becoming inundated with water due to the high water table and heavy rains could also be minimised. In addition, there is a need to improve sanitation by provision of toilets and underground sewers for safe disposal of human waste. Sanitation challenges also arise from a lack of education and awareness

as is the case when observing reluctance to evacuate or even relocate. The study highlights differing perspectives of communities and local authorities when challenges were identified. Infrastructure interventions by the Government need to be supported by public awareness campaigns about the risks of flooding, appropriate and safe practices for sanitation and waste disposal, and evacuation from the area. The involvement of the City council and INGC is required to gain community trust and urge residents to comply with evacuation procedures, as well as playing an active role in improving drainage channels and road conditions across the settlement. An effective flood mitigation strategy for Maxaquene A requires close collaboration with the local community and stakeholders in Maputo that will build on the local knowledge and practices of communities. INGC produced a summary report which emphasized the need for collaboration between sectors for water supply and sanitation services, improved accessibility through road works and measures to protect housing stock (OCHA, 2001). It is possible for the conclusions of this paper to act as an introductory piece to governmental agencies and NGOs carrying out interventions in Maputo's settlements paving the way to drive change in development practice and future interventions across the city. Recent flooding events and the resulting devastation associated with Cyclone Idai reinforce the urgent need to work closely with communities to prioritise climate change adaptation plans for informal settlements in Maputo.

Putting a single informal settlement under the microscope helps to dissect the everyday problems faced by residents, but also understand how history, urban growth and migration have affected the landscape. With these local stories and identification of challenges there is now scope to develop a comparative study of informal settlements globally. This will help to move towards a more inclusive climate adaptation agenda, where the marginalised and least represented are considered equally on the same platform as other citizens. UN-Habitat (2010) estimates that by 2030 over 3 billion people (40% of the world's population) will require adequate housing and access to basic infrastructure. With such large numbers upgrading infrastructure will enhance environmental conditions for slum dwellers and improve living conditions.

This research focuses on the lives of the residents of Maxaquene A and challenges arising from frequent floods in their informal settlement. This rapid assessment methodology can easily be replicated in other cities and regions of the world where such disasters are frequent. In particular, for sub-Saharan Africa, most informal settlements are situated on less habitable, low-lying areas of the city and have high population densities, creating a similar environment for infrastructural and service challenges. Where similarities in challenges are identified, solutions that address issues - like poor solid waste collection, lack of functioning drainage channels, adequate sanitation - can be replicated across settlements.

Strengths and weaknesses of the methodology

The study was a rapid assessment that was not resource intensive, but nonetheless was successful in drawing out gaps in infrastructure services and impact of flooding on everyday lives of local communities. The methodology is easily replicable in other neighbourhoods where infrastructural assessment is required not only for flooding, but also other types of natural and environmental disasters. The combination of desk-based research with fieldwork consisting of transect walks, community workshop and interviews with locals and external partners helps to gain a multifaceted understanding of the neighbourhood and its challenges. This rapid assessment managed to bring to the forefront challenges faced by local communities on a day-to-day basis providing valuable information for policy makers and other stakeholders.

It should be noted that the scale of this methodology and research project remains small – with the spotlight on one neighbourhood in Maputo. In order to provide a deeper analysis of the region, comparing infrastructure and services with other settlements, like Chamanculo (a settlement mentioned by the residents) will help gain a more rigorous understanding of the challenges; it could also help in understanding the extent to which the topography, interaction between stakeholders and local government, and settlement history and density play a role in adaptation to frequent floods. Furthermore, the project involved activities like transect walks, interviews and community workshops, but only one of each was conducted; to gain further insight and a diversity of experiences and opinions it would be useful to hold multiple workshops and transect walks, and interview a larger sample of people. Alongside this, repeating the fieldwork at different points of time in the year (in different seasons, for example) could assist in understanding how the intensity of torrential rainfall and flooding may differ. Moreover, comparing such cases with those of other settlements in cities in sub-Saharan Africa will shed a light on governance, policy and the urban development agenda in different countries.

References

- ActionAid International. 2006. *Unjust Waters*. London. Retrieved (https://www.actionaid.org.uk/sites/default/files/doc_lib/unjust_waters.pdf).
- Adeagbo, A., Daramola, A., Carim-Sanni, A., Akujobi, C. and Ukpong, C., 2016. Effects of natural disasters on social and economic well being: A study in Nigeria. *International journal of disaster risk reduction*, 17, pp.1-12.
- Artur, L. and Hilhorst, D., 2012. Everyday realities of climate change adaptation in Mozambique. *Global Environmental Change*, 22(2), pp.529-536.
- Azuma, K et al. 2014. "Effects of Water-Damaged Homes after Flooding: Health Status of the Residents and the Environmental Risk Factors." *International Journal of Environmental Health Research* 24(2):158–75. Retrieved (<http://www.tandfonline.com/doi/abs/10.1080/09603123.2013.800964>).
- Bouchard, B., Goncalo, A., Susienka, M., Wilson, K., Weininger, S., Jiusto, S., Wood, B. and Kenny, M., 2007. *Improving flood risk management in informal settlements of Cape Town* (Doctoral dissertation, Worcester Polytechnic Institute (WPI)).
- Campos, L.C., Ross, P., Nasir, Z.A., Taylor, H. and Parkinson, J., 2015. Development and application of a methodology to assess sanitary risks in Maputo, Mozambique. *Environment and Urbanization*, 27(2), pp.371-388.
- Carrilho, Júlio et al. 2010. *Mozambique Cities Profile*. Nairobi.
- Castán Broto, V., Oballa, B. and Junior, P., 2013. Governing climate change for a just city: challenges and lessons from Maputo, Mozambique. *Local Environment*, 18(6), pp.678-704.
- Castan Broto, V., Boyd, E. and Ensor, J., 2015. Participatory urban planning for climate change adaptation in coastal cities: lessons from a pilot experience in Maputo, Mozambique. *Current Opinion in Environmental Sustainability*, 13, pp.11-18.
- Chambers, R., 1994. The origins and practice of participatory rural appraisal. *World development*, 22(7), pp.953-969.
- Degert, I., Parikh, P. and Kabir, R., 2016. Sustainability assessment of a slum upgrading intervention in Bangladesh. *Cities*, 56, pp.63-73.
- Doocy, S., Daniels, A., Packer, C., Dick, A. and Kirsch, T.D., 2013. The human impact of earthquakes: a historical review of events 1980-2009 and systematic literature review. *PLoS currents*, 5.
- Fairhurst, L., Rowsell, P. and Nhleko, L., 2011. Sub-Saharan African cities: A five city network to pioneer climate adaptation through participatory research and local action. Baseline study.
- Few, R., 2003. Flooding, vulnerability and coping strategies: local responses to a global threat. *Progress in Development Studies*, 3(1), pp.43-58.
- Fitchett, A., 2014, September. Adaptive co-management in the context of informal settlements. In *Urban Forum* (Vol. 25, No. 3, pp. 355-374). Springer Netherlands.
- Grahn, T. and Nyberg, L., 2017. Assessment of pluvial flood exposure and vulnerability of residential areas. *International Journal of Disaster Risk Reduction*, 21, pp.367-375.
- INGC. 2006. *Master Plan For Prevention and Mitigation of Natural Disasters*. Maputo.
- Jha, A.K., Bloch, R. and Lamond, J., 2012. *Cities and flooding: a guide to integrated urban flood risk management for the 21st century*. World Bank Publications.
- Kayaga, S., Godfrey, A., Cotton, A. and Costa, C.B., 2015. Improving on-plot sanitation management in low-income settlements of cities of developing countries: case study from Maputo, Mozambique. *International Journal of Environment and Waste Management*, 16(2), pp.112-132.
- Kemp, L. et al., 2011. Sub-Saharan African Cities: A five-City Network to Pioneer Climate Adaptation through Participatory Research and Local Action - Maputo Baseline Study, Maputo: ICLEI - Local Governments for Sustainability - Africa.
- Kita, S.M., 2017. Urban vulnerability, disaster risk reduction and resettlement in Mzuzu City, Malawi. *International Journal of Disaster Risk Reduction*, 22, pp.158-166.
- Kruks-Wisner, G., 2006. *After the flood: crisis, voice and innovation in Maputo's solid waste management sector* (Doctoral dissertation, Massachusetts Institute of Technology).
- Kwadijk, Jaap CJ, Marjolijn Haasnoot, Jan PM Mulder, Marco Hoogvliet, Ad Jeuken, Rob AA van der Krogt, Niels GC van Oostrom et al. "Using adaptation tipping points to prepare for climate change and sea level rise: a case study in the Netherlands." *Wiley Interdisciplinary Reviews: Climate Change* 1, no. 5 (2010):

- Noosorn, N. and Niamkamnerd, P., 2009. Public participation to minimize waterborne diseases in Yom riverside communities. *Journal of Public Health and Epidemiology*, 1(1), pp.037-040.
- Office for the Coordination of Humanitarian Affairs (OCHA), 2001. "Mozambique Floods 2001 – Lessons Learned" Workshop 26-27 July 2001 Beira. Summary Report produced by the Office of the United Nations Resident Coordinator Maputo.
- Padawangi, R., Turpin, E., Prescott, M.F., Lee, I. and Shepherd, A., 2016. Mapping an alternative community river: The case of the Ciliwung. *Sustainable Cities and Society*, 20, pp.147-157.
- Palalane, J., 2010. Comparative analysis of sub-surface drainage solutions in Maxaquene "A".
- Parikh, P., Parikh, H. and McRobie, A., 2012. The role of infrastructure in improving human settlements. *Proceedings of the Institution of Civil Engineers-Urban Design and Planning*, 166(2), pp.101-118.
- Royo, M.G., Parikh, P., Mutwiri, F., Harper, J., Bukachi, V. and Mulligan, J., 2018. Using Future Scenario Planning as a tool for informed decision making on infrastructure interventions in Kibera, Nairobi in Kenya. *Habitat International*, 79, pp.30-41.
- Sakijege, T., Lupala, J. and Sheuya, S., 2012. Flooding, flood risks and coping strategies in urban informal residential areas: The case of Keko Machungwa, Dar es Salaam, Tanzania. *Jambá: Journal of Disaster Risk Studies*, 4(1), pp.1-10.
- UN-Habitat, 2010. Climate change assessment for Maputo, Mozambique. *Cities and Climate Change Initiative. Nairobi, Kenya*. <https://unhabitat.org/books/climate-change-assessment-for-maputo-mozambique/>
- UN-Habitat, 2016. Slums Almanac 2015–16. *Tracking Improvement in the Lives of Slum Dwellers*.
- United Nations Development Programme (UNDP) (2010) Disaster Risk Assessment in Mozambique - A Comprehensive Country Situation Analysis, Global Risk, Identification Programme, accessed in April 2018 from <https://www.geonode-gfdrmlab.org/documents/797/download>.
- United National Economic Commission for Africa (UNECA), 2015 Assessment report on mainstreaming and implementing disaster risk reduction in Mozambique, Addis Ababa,
- Van Logchem, B. & Queface, A.J. (eds.). 2012. Responding to Climate Change in Mozambique: Synthesis Report. Maputo INGC.
- WIN-SA. 2012. "2nd International Faecal Sludge Management Conference." P. 57 in, edited by Water Information Network- South Africa (WIN-SA). Durban: Water Research Commission.
- Woolf, S., Twigg, J., Parikh, P., Karaoglou, A. and Cheaib, T., 2016. Towards measurable resilience: A novel framework tool for the assessment of resilience levels in slums. *International Journal of Disaster Risk Reduction*, 19, pp.280-302.