

1 **BIM-based task and motion planning prototype for robotic assembly of COVID-19**  
2 **hospitalisation units—flatpack house**

3 Yifan Gao<sup>a,c,d</sup>, Jiawei Meng<sup>b</sup>, Jiangpeng Shu<sup>a,\*</sup>, Yuanchang Liu<sup>b</sup>

4 <sup>a</sup> College of Civil Engineering and Architecture, Zhejiang University, Hangzhou 310058, China

5 <sup>b</sup> Department of Mechanical Engineering, University College London, London WC1E 6BT,  
6 The United Kingdom

7 <sup>c</sup> Center for Balance Architecture, Zhejiang University, Hangzhou 310058, China

8 <sup>d</sup> The Architectural Design & Research Institute of Zhejiang University Co. Ltd, Hangzhou  
9 310028, China

10 \* Corresponding author at 866, Yuhangtang Road, Hangzhou, Zhejiang 310058, China

11 Email address: [jpeshu@zju.edu.cn](mailto:jpeshu@zju.edu.cn) (Jiangpeng Shu, corresponding author)

12 [yfgao91@zju.edu.cn](mailto:yfgao91@zju.edu.cn) (Yifan Gao)

13 [jiawei.meng@ucl.ac.uk](mailto:jiawei.meng@ucl.ac.uk) (Jiawei Meng)

14 [yuanchang.liu@ucl.ac.uk](mailto:yuanchang.liu@ucl.ac.uk) (Yuanchang Liu)

15 **BIM-based task and motion planning prototype for robotic assembly of COVID-19**  
16 **hospitalisation units—flatpack house**

17 **Abstract:** Fast transmission of COVID-19 led to mass cancelling of events to contain the virus  
18 outbreak. Amid lockdown restrictions, a vast number of construction projects came to a halt.  
19 Robotic platforms can perform construction projects in an unmanned manner, thus ensuring the  
20 essential construction tasks are not suspended during the pandemic. This research developed a  
21 BIM-based prototype, including a task planning algorithm and a motion planning algorithm, to  
22 assist in the robotic assembly of COVID-19 hospitalisation facilities with prefabricated  
23 components. The task planning algorithm can determine the assembly sequence and coordinates  
24 for various types of prefabricated components. The motion planning algorithm can generate  
25 robots' kinematic parameters for performing the assembly of the prefabricated components.  
26 Testing of the prototype finds that it has satisfactory performance in terms of 1) the  
27 reasonableness of assembly sequence determined, 2) reachability for the assembly coordinates  
28 of prefabricated components, and 3) capability to avoid obstacles.

29 **Keywords:** Building information modelling, robotic construction, hospitalisation facility,  
30 COVID-19 pandemic, motion planning.

31 **1. Introduction**

32 The pandemic caused by COVID-19 is the most serious global health crisis during the past  
33 decades due to the rapid growth in confirmed cases and a massive spike in hospitalisations [1].  
34 To prevent the further spread of the virus, China built two new hospitals (*Leishenshan* and  
35 *Huoshenshan*) in Wuhan and also converted existing facilities to 16 module hospitals [2]. These  
36 measures effectively reduced the number of death and the spread of the virus [3]. Following  
37 these examples, the UK also turned convention centres into seven Nightingale hospitals [4].  
38 Nevertheless, numerous reports from different world regions indicate that many patients have  
39 limited access to treatment due to the shortage of hospitalisation facilities [5]. As COVID-19  
40 still looms as a significant threat to human beings, critical infrastructure for pandemic isolation  
41 and treatment remains far from adequate globally [3].

42 The current method for constructing the COVID-19 hospitalisation facilities is by having  
43 human workers assemble each prefabricated component (e.g., purlin, pillar, beam) into  
44 designated coordinates [2]. However, under the pandemic lockdown situation, it becomes  
45 difficult for workers to access the site and conduct construction activities, and a vast number of  
46 construction projects have come to a halt [6]. As the Associated General Contractors (AGC) in  
47 the US pointed out [7], nearly 90% of the US domestic construction projects were put on hold  
48 in 2020, and more than 27% of the construction organisations have either furloughed or laid off  
49 employees in 2021. As a result, a certain number of COVID-19 healthcare projects, which  
50 should have been constructed to provide the treatment spaces for the infected patients, were not  
51 delivered in time [7]. Consequently, technologies that can enable the unmanned assembly of  
52 hospitalisation facilities from prefabricated components are in urgent need. This spawns the  
53 idea in this research to develop robotic technologies for assembling COVID-19 hospitalisation  
54 facilities.

55 In the literature, empirical evidence has been provided that the use of robotic technologies  
56 has the potential to replace human labour and alleviate the impact of lockdown restrictions on  
57 the construction progress [8–11]. The evidences are from industry survey [12], systematic  
58 review [13–16], mechanical design [17–20], prototype and methodology development [8–  
59 11,21–23], algorithmic design [18,19], and commentary [8,24,25]. In these literature, the  
60 studies by Terada and Murata [8], Willmann et al. [9], Ding et al. [10], and King et al. [11] are  
61 found to have a similar scientific focus to this research—utilising robots to assemble  
62 prefabricated building components. Terada and Murata [8] utilised a robotic manipulator to  
63 assemble building blocks. Willmann et al. [9] designed a robotic prototype for timber  
64 construction, which fosters automation penetration across the digital workflow including timber  
65 fabrication, perforation, and connection. Ding et al. [10] and King et al. [11] presented methods  
66 that can determine assembly coordinates of building components for robotic construction  
67 according to digital blueprints in Rhinoceros.

68 The COVID-19 hospitalisation facilities are composed of container-type units—flatpack  
69 house, where each flatpack house unit is a ward [2]. The current method to assemble the flatpack  
70 house units of COVID-19 hospitalisation facilities consists of the following characteristics.

71 First, there is a fixed sequence for the assembly of the flatpack house unit. The structural frame  
72 is assembled first (including the beam, column, and purlin components). Once the frame is in  
73 place, the floor and roof panels are assembled next. Then, the wall panels are attached. This is  
74 interpreted in greater detail in section 2. Second, the prefabricated components of the flatpack  
75 house are made from lightweight steel, which is more suitable for robot assembly compared  
76 with components that are made from dense materials such as concrete. However, applying  
77 robots to replace human labour in the assembly of flatpack house, there are still difficulties that  
78 await to be addressed. The difficulties lie in letting the end-tip of the robot autonomously follow  
79 a pre-determined sequence to place the prefabricated components in coordinates where they are  
80 needed in space without human intervention. The authors found that the robotic approaches  
81 developed in the existing studies [8–11] (as aforementioned) have limited usability for  
82 addressing the technical difficulties in assembling flatpack house, given the lack of the  
83 following capabilities:

- 84 • *Pre-determining the assembly sequence of building components.* In the existing studies [8–  
85 11], the assembly coordinates of prefabricated building components were predetermined  
86 for the robotic assembly. However, the function of determining the assembly sequence of  
87 the prefabricated building components was not considered in their approaches. In such a  
88 case, workers are still needed to collaborate with the robotic platforms to manually input  
89 the coordinates for the assembly of each building component respectively. Given the  
90 pandemic lockdown situation, the robotic assembly of the hospitalisation facilities is  
91 expected to be performed automatically without human intervention. The challenge of such  
92 a solution lies in the generation of a reasonable assembly sequence of building components,  
93 and then the end-tip of the robot can follow the pre-determined sequence to place building  
94 components in coordinates where they are needed in space [23]. Therefore, quantitative  
95 spatial reasoning of the building components' assembly sequence is a critical issue to  
96 consider for the robotic assembly of the hospitalisation facilities.

97 Given the background, the scientific question of the study is how to determine a  
98 mathematical relationship between coordinates of prefabricated components and assembly  
99 sequence, with the consideration of their geometry and centroid, for robotic construction.

100 Therefore, this research aims to overcome the technical challenges and provide a robotic  
101 prototype that consists of the following:


- 102 1) A task planning algorithm that can determine a mathematical relationship between  
103 coordinates of prefabricated components and assembly sequence, with the consideration  
104 of geometry and centroid, for robotic construction; and
- 105 2) A motion planning algorithm that can analyse the determined assembly sequence and  
106 coordinates and generate robots' kinematic parameters for performing the assembly of  
107 COVID-19 hospitalisation facilities.

108 In addition, in the research field of industrial robot, there are a number of recently  
109 published studies that have reported the data transmission between product design data and  
110 robotic platforms for manufacturing such as Tao et al. [26], Jokić et al. [27], Izagirre et al. [28],  
111 Zhang et al. [29], and Li et al. [30]. However, the authors found that there is still relatively little  
112 information on the data penetration between the building digital designs and robotic platforms.  
113 This research aims to fill in the gap and investigate the data operation method in the proposed  
114 robotic prototype for facilitating the information penetration between the building digital  
115 designs and robotic platforms.

116 The rest of the paper is organised as follows: section 2 demonstrates the construction  
117 characteristics of COVID-19 hospitalisation facilities, section 3 presents the overall  
118 architecture of the proposed prototype, section 4 illustrates the configuration of the robotic  
119 platform, section 5 interprets the task planning algorithm, section 6 interprets the motion  
120 planning algorithm, section 7 demonstrates the testing results of the developed prototype,  
121 section 8 discusses the theoretical and practical implications, while section 9 summarises the  
122 findings, notes the limitations, and recommends future research directions.

## 123 **2. Demonstration of COVID-19 hospitalisation facilities**


124 As documented in Luo et al. [2], the COVID-19 hospitalisation facilities of *Leishenshan*  
125 hospital in Wuhan, China are composed of more than 3000 container-type units—flatpack  
126 house. Each flatpack house unit is a ward, which has a standard size of 6.0 meters long, 3.0  
127 meters wide, and 2.6 meters tall and consists of prefabricated components including purlins,  
128 beams, columns, and panels [2] (see Figure 1).



**Figure 1.** The standard flatpack house unit utilised in *Leishenshan* hospital.

129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144

According to Luo et al. [2] and industrial professionals' depiction, the current method to construct the *Leishenshan* hospitalisation facilities consisted of the following characteristics. First, the flatpack house units were assembled on-site and piece by piece (by human workers) from prefabricated components that were made in advance in a factory. Second, the flatpack house units were hoisted into the designated location and lined up side by side (by a mobile crane). In Figure 2, the authors utilise a computer-simulated environment to illustrate the construction procedure. As can be seen, a truck transports the prefabricated components from the factory to the building site, and worker (A) unloads the components from the truck and stores them in the trolley. Then worker (B) assembles the flatpack house using prefabricated components in the trolley. Specifically, the assembly of the flatpack house is threefold. The structural frame is assembled first (including the beam, column, and purlin components). Once the frame is in place, the floor and roof panels are assembled next. Then, the wall panels are attached. When the assembly completes, a mobile crane is used to lift the flatpack house unit from the assembling area and install the unit into the hoisting area.



**Figure 2.** The *Leishenshan* hospital construction procedure (illustrated in a computer-simulated environment).

Information on the material and mass of the prefabricated components as well as the number of each component used in a flatpack house is provided in Table 1. According to the information, it is estimated that a flatpack house has an overall weight of 969.2 kg. This exceeds the handling capacity of the top-size industrial robotic manipulator on the market—ABB IRB 8700 (rated payload: 500kg). Mobile cranes might be more suitable than robotic manipulators for the installation of the standard flatpack house unit at the designated location. Therefore, this research focuses on robotising the first stage of hospitalisation facilities construction— assembling the flatpack house from prefabricated components. Note that this research focuses on the robotic assembly of structural components (see Table 1), and does not involve the installation of mechanical, electrical, and plumbing parts. The robot will replace human labour in the assembly process, where the construction difficulties lie in letting the end-tip of the robot autonomously follow a pre-determined sequence to place the prefabricated components in coordinates where they are needed in space without human intervention. To achieve the targeted performance for the robot, a task planning algorithm and a motion planning algorithm will be developed to respectively: 1) determine reasonable assembly coordinates and sequence of prefabricated components; and 2) analyse the determined assembly sequence and generate

164 robots' kinematic parameters for performing the assembly of COVID-19 hospitalisation  
 165 facilities autonomously without human intervention. Note that the sequence will be determined  
 166 in accord with the threefold assembly logic as specified (i.e., first the frame, next the floor and  
 167 roof panels, then the wall panels).

168 **Table 1.** Material and mass of prefabricated components, and the number of each component  
 169 used in a unit.

<b>Component</b>	<b>Material</b>	<b>Mass (kg)</b>	<b>Number</b>
Beam (Long Edge)	Galvanised Steel	55.7	4
Beam (Short Edge)	Galvanised Steel	27.1	4
Column	Galvanised Steel	20.7	4
Purlin	Galvanised Steel	4.8	18
Wall Panel	Metal-skinned Polystyrene	12.9	18
Floor (Roof) Panel	Metal-skinned Polystyrene	16.9	14


### 170 3. System overview of the proposed prototype

171 This research explores how the COVID-19 hospitalisation facilities can be assembled from  
 172 prefabricated components using robotic manipulators. As discussed, the motion control of a  
 173 robotic manipulator consists of letting the tip of the end-effector follow a pre-determined  
 174 “sequence” of “coordinates”. Thus, the challenge of such a solution lies in the generation of a  
 175 reasonable assembly “sequence” of building components, and the precise, automated placement  
 176 of building components in “coordinates” where it is needed in space. To provide a prototype  
 177 that can outplay the challenges, this research considers expanding the digital blueprint of the  
 178 COVID-19 hospitalisation facilities in BIM into robotic control instructions. The process  
 179 generates a task planning algorithm and a motion planning algorithm. As Ding et al. [10]  
 180 pointed out, BIM projects contain large quantities of spatial information that can be used to  
 181 serve build-up activities. For example, BIM projects are composed of loadable families (known  
 182 as the “library components”), which are the graphical representations of prefabricated building  
 183 components [19] (Figure 3a). To create a BIM project, the families are spatially integrated  
 184 (Figure 3b). The process of integrating families into a unifying BIM project creates  
 185 georeferenced properties that are useful for determining the assembly coordinates and sequence




186 of building components.

(a)



187

(b)




188

189 **Figure 3.** BIM project creation: (a) BIM loadable families; (b) spatial integration of loadable

190

families into BIM.

191 BIM design tools (e.g., Autodesk Revit) host informative databases for their projects,  
 192 where Application Programming Interface (API) (e.g., Dynamo) can be utilised to couple with,  
 193 and democratise, the database for end-users to get access to data and retrieve desired features  
 194 [31]. In this research, Dynamo and the Robot Operating System (ROS) were utilised to develop  
 195 the robotic prototype for assembling the prefabricated hospitalisation facilities, where  
 196 Dynamo's role is to provide the required data input for ROS. A Dynamo-based task planning  
 197 algorithm was developed to locate the assembly coordinates of the building components in the  
 198 flatpack house Revit model and then generate a reasonable assembly sequence of the  
 199 components based on their coordinates. The assembly sequence data constitutes the information  
 200 required for the robotic motion planning. Then, the Robot Operating System (ROS) executes  
 201 the motion planning algorithm to analyse the assembly sequence data and generate robots'  
 202 kinematic parameters for performing the assembly of the flatpack house (including the joint  
 203 and path parameters). A communication interface was also established to operate the data  
 204 transmission between the task and motion planning layers. An overview of the architecture of  
 205 the proposed prototype is provided in Figure 4. The detailed steps are discussed in sections 4-7  
 206 below.




207  
 208


**Figure 4.** An overview of the architecture of the proposed prototype.

209 **4. Configuration of the robotic platform**

210 The workspace and payload of a robotic manipulator determine if the manipulator is suitable  
211 for certain construction tasks [23]. Workspace is the set of all positions that a manipulator can  
212 reach, which constitutes a reachable volume between the maximum and minimal working  
213 radius of the manipulator [32] (see Figure 5a). However, it was found that when having one  
214 side of the flatpack house placed as close as possible to the minimal working radius, the  
215 workspace of the top size industrial robotic manipulator on the market—ABB IRB 8700 (work  
216 range: 4157mm, rated payload: 500kg)—still cannot fully cover the spatial extent of the  
217 flatpack house for assembly, with the far end being out of reach (see Figure 5a). In this case,  
218 collaborative construction using dual robotic manipulators—KUKA KR 120 R3100 (work  
219 range: 3095mm, rated payload: 120kg)—is considered (see Figure 5b). To provide a reasonable  
220 range of workspace for assembling COVID-19 hospitalisation facilities, the manipulators are  
221 mounted on KUKA KL 4000 linear unit (maximum translational distance: 8500mm) [33].  
222 Payload is the amount of matter (i.e., mass) that a manipulator can lift [32]. As can be seen in  
223 Table 1, the beam (long edge) is the structural component that has the maximal mass (i.e.,  
224 55.7kg). Thus, the manipulator to use in this research should meet the criterion of having its  
225 payload exceed 55.7kg. The rated payload of KR 120 R3100 is 120kg, which meets the criterion  
226 and is robust for the assembly of the flatpack house in this research.



227



228

229

**Figure 5.** Robotic platforms: (a) ABB IRB 8700; (b) KUKA KR 120 R3100.

230

231

232

233

234

235

236

237


238

239

240

241

The robotic manipulator used in this research is composed of one prismatic joint and six revolute joints (i.e., seven degree-of-freedom (DOF)). A revolute joint enables a relative rotary motion about an axis, and a prismatic joint translates a linear displacement along an axis [34]. Kinematic specification of the joints is presented in Figure 6. Motion range of the joints is provided by KUKA [35] as follows: joint 1 (from 0 to 8.500 m), joint 2 (from -3.227 to 3.227 rad), joint 3 (from -1.483 to 0.872 rad), joint 4 (from -1.361 to 2.093 rad), joint 5 (from -6.106 to 6.106 rad), joint 6 (from -2.181 to 2.181 rad), and joint 7 (from -6.106 to 6.106 rad). The motion range will be utilised as joint constraints for kinematic analytics in this research. The COVAL vacuum gripper is connected to the main body of the manipulator through a flange, which is the end effector and operates utilising vacuum adsorption to hoist building components [36] (Figure 6). The gripper is designed for heavy-duty applications and can withstand a weight of up to 68kg.




242

243

**Figure 6.** Kinematic specification of the joints.

244 **5. Task planning algorithm: determining assembly coordinates and sequence**

245 In this research, the task planning logic to bring into effect is locating the placement coordinates  
 246 of the building components for assembly and then generating a reasonable assembly sequence  
 247 of the components based on their coordinates. The authors utilised the Autodesk Revit API—  
 248 Dynamo—to develop the task planning algorithm, which is named the Assembly Coordinates  
 249 and Sequence Determination (ACASD) algorithm. Dynamo is a visual programming  
 250 environment that extends the parametric analysis capabilities of Revit [37]. The analytic  
 251 capability of Dynamo is enabled through functional nodes, which are composed of input and  
 252 output ports and are connected in sequence to form a complete logic [37] (see Figure 7). Users  
 253 can compile in Python to create nodes for specific functions [31] (e.g., *Assembly Sequence ()*  
 254 in Figure 7). The compositions of the ACASD algorithm are presented in Figure 7 and  
 255 Algorithm 1 below. As can be seen, the algorithm consists of three sections, which are discussed  
 256 in greater detail in the following paragraphs.



257

258 **Figure 7.** The architecture of the Assembly Coordinates and Sequence Determination

259

(ACASD) algorithm.

---

**Algorithm 1:** Assembly Coordinates and Sequence Determination (ACASD) Algorithm

---


```

orglst ← categories(structural framing);
orglst ← categories(Structural Columns);
orglst ← categories(Floors);
orglst ← categories(Walls);
orglst ← orglst.Geometry();
orglst ← orglst.Centroid();
sortbyZYX(orglst):
    |   orglst.sort(key = lambda orglst: (orglst.Z, orglst.Y, orglst.X));
    |   return orglst;
end
input ← IN[0];
for i in input:
    |   if i.categories() != Walls:
    |       |   result_frame ← append(sortbyZYX(i));
    |   else:
    |       |   result_wall ← append(sortbyZYX(i));
end
OUT ← {result_frame, result_wall}

```

---

260 Section 1 of the algorithm seeks to let Dynamo identify all building components from the  
261 Revit model in Figure 3b. This is enabled by nodes *Categories ()* and *All Elements of Category*  
262 *()* (Figure 7). *Categories ()* returns the names of structural categories that form the Revit model  
263 (e.g., framing, columns, floors). In Revit, the cache keeps track of the building components by  
264 attaching a unique identifier ID to each component. *All Elements of Category ()* can read the  
265 identifier IDs of all components of the returned categories. The reading result is passed to the  
266 *List Create ()* node, which creates a list of the identified components' IDs (Figure 7). Using the  
267 nodes *Element.Geometry ()* and *Solid.Centroid ()*, section 2 of the algorithm is designed to  
268 locate the identified components in the Revit model's coordinate system (Figure 8).  
269 *Element.Geometry ()* takes the list of the identified components' IDs and retrieves the geometry  
270 associated with the IDs from Revit. *Solid.Centroid ()* then detects the vertexes of each geometry,  
271 computes the centroid for each geometry by averaging the sums of the coordinates of the  
272 vertexes, and plots the centroid (represented by black dots in Figure 8). The origin of the  
273 reference frame for describing the centroid coordinates was set at the bottom-left corner of the  
274 flatpack house (blue arrow—z-axis, red arrow—x-axis, and green arrow—y-axis) (Figure 8).




275  
276 **Figure 8.** Centroids of the building components are plotted in Dynamo.

277 Section 3 of the algorithm concerns the creation of a reasonable assembly sequence for the  
278 building components. The procedure for constructing a flatpack house can be presented as a  
279 sequence of subtasks [2]: the frame is first assembled and then the wall panels are enclosed


280 (Figure 9a). The frame consists of bottom and top frames as transverse bearing constitution and  
 281 columns as vertical supporting (Figure 9a), where the assembly sequence incorporates the  
 282 bottom-to-top, left-to-right, and back-to-front processing (Figure 9b). The processing derives a  
 283 vector that points along in sequence the z-axis, the y-axis, and the x-axis. Given that the size of  
 284 the flatpack house is 6.0 meters long, 3.0 meters wide, and 2.6 meters tall [2], the vector  $\vec{u} =$   
 285  $\vec{z} + \vec{y} + \vec{x} = (0, 0, 2.6) + (0, 6, 0) + (3, 0, 0) = (3, 6, 2.6)$  (Figure 9b). The node *Assembly*  
 286 *Sequence ()* in section 3 was defined to derive the vector  $\vec{u}$  as introduced. When running the  
 287 *Assembly Sequence ()* node, the vector  $\vec{u}$  is applied to detecting in sequence the z-, y-, then x-  
 288 coordinate values of the building components' centroids. This process first generates a list of  
 289 building components arranged in ascending order along the z-axis (from the bottommost to the  
 290 topmost). Then, for components that indicate the same size of z-coordinate values, the left-to-  
 291 right, back-to-front procedure makes inferences to sort the components along the y-axis (from  
 292 the leftmost to the rightmost), then the x-axis (from the rearmost to the foremost). Following  
 293 the process, the assembly sequence for the frame is determined. For wall panels, the assembly  
 294 sequence is determined in the same manner.

295 (a)



296






298 **Figure 9.** Assembly process of a flatpack house: (a) the frame and wall sequence; (b) the  
 299 bottom-to-top, back-to-front, left-to-right processing.

300 The output of the *Assembly Sequence ()* node is: “result\_frame = []; result\_wall = []; OUT  
 301 = result\_frame + result\_wall”. The “result\_frame” paradigm contains the centroid coordinates  
 302 of the frame components sorted in the assembly sequence order. The “result\_wall” paradigm  
 303 contains the centroid coordinates of the wall panels sorted in the assembly sequence order. The  
 304 “OUT = result\_frame + result\_wall” paradigm indicates that the sortation of frame components  
 305 comes before the listing of wall panels’ centroid coordinates. This is consistent with the aimed  
 306 assembly sequence that the frame is first assembled and then the wall panels are enclosed.  
 307 Subsequently, the outputs are supplemented to form an analysable data file for the ROS  
 308 executions, which constitutes the information required for the robotic motion planning. This  
 309 research used Industry Foundation Classes (IFC) as the interoperable data format between the  
 310 task planning layer (in BIM) and the motion planning layer (in ROS).

311 The communication interface in Figure 10 was designed for data transmission between the  
 312 task and motion planning layers, which is enabled by functional nodes at Dynamo, IFC and  
 313 ROS terminals. First, the node *Export\_IFC ()* at the Dynamo terminal takes the sorted assembly  
 314 sequence list and exports it to an IFC file. Then, the node *IfcAxis2Placement3D ()* at IFC  
 315 terminal organises data entries in a string form that can be parsed by the ROS system as follows:  
 316 “#IFC Identifier = ifcPropertyStringValue(Parameter Label).placement(Parameter Content)”

317 (see Figure 10). The node *Subscriber ()* at the ROS terminal is responsible for parsing the  
 318 assembly coordinates and sequence data from the IFC tags. The robots' joint and trajectory  
 319 parameters for performing the assembly of the prefabricated components will be generated  
 320 based on the IFC data provided (see "Joint Interface" and "Trajectory Interface" in Figure 10).  
 321 Finally, the node *Publisher ()* at the ROS terminal publishes the generated joint and trajectory  
 322 parameters for controlling the robotic manipulator.




323  
 324 **Figure 10.** Communication interface for data transmission between the task and motion  
 325 planning layers.

326 **6. Motion planning algorithm: generating kinematic parameters while avoiding**  
 327 **obstacles**

328 The kinematic equation is fundamental to robotic motion planning, which can be used to  
 329 compute values for the joints that achieve a desired position for the end-tip of a manipulator  
 330 [34]. To derive the kinematic equation of the manipulator used in this research, reference frames,  
 331 which are used to specify movements of each joint, were attached to the joints (as specified in

332 Figure 6) following the right-hand convention rules [38,39] (Figure 11).



333

334

**Figure 11.** Reference frames are attached to the robotic manipulator.

335

The pose relationship (i.e., position and orientation) between two successive joints can be derived from attached frames using Denavit-Hartenberg (D-H) notation [40]. DH notation consists of four transformation parameters  $d_i$ ,  $\theta_i$ ,  $a_i$ , and  $\alpha_i$  (see Figure 11), which gives a standard methodology to write the kinematic equations of a robotic manipulator [40]. The parameter  $d_i$  notates the linear displacement along z-axis in the  $i$ th frame. The parameter  $\theta_i$  notates the rotary angle around the z-axis in the  $i$ th frame. The parameter  $a_i$  notates the link length between  $i$ th and  $i + 1$ th frames along the x-axis in the  $i$ th frame. The parameter  $\alpha_i$  notates the twist angle between the z-axes in the  $i - 1$ th and  $i$ th frames. For the 7 DOF manipulator,  $d_i$  and  $\theta_i$  are variables altering as the joints operate, and  $a_i$  and  $\alpha_i$  are constants reflecting the mechanical structure of the manipulator (e.g., link length) (see Table 2).

344

345

**Table 2.** D-H parameters of 7 DOF robotic manipulator.

$i$ th frame (joint)	$d_i$ (m)	$\theta_i$ (rad)	$a_i$ (m)	$\alpha_i$ (rad)
1 (prismatic)	$d_1$	0	$a_1 = 1.334$	0
2 (revolute)	0	$\theta_2$	$a_2 = 0.330$	$\alpha_2 = 1.570$
3 (revolute)	0	$\theta_3$	$a_3 = 1.350$	$\alpha_3 = 1.570$
4 (revolute)	0	$\theta_4$	$a_4 = 0.115$	$\alpha_4 = 1.570$

5 (revolute)	0	$\theta_5$	$a_5 = 1.420$	$\alpha_5 = 1.570$
6 (revolute)	0	$\theta_6$	$a_6 = 0.308$	$\alpha_6 = 1.570$
7 (revolute)	0	$\theta_7$	0	$\alpha_7 = 1.570$

346 The transformations (i.e.,  $d_i$ ,  $\theta_i$ ,  $a_i$ , and  $\alpha_i$ ) along the serial frames form the kinematic  
347 equation ( $T$ ), which were derived by multiplying the homogeneous transformation matrices of  
348  $d_i$ ,  $\theta_i$ ,  $a_i$ , and  $\alpha_i$  [40]:

$$349 \quad T = \prod_{i=1}^7 \begin{bmatrix} \cos(\theta_i) & -\sin(\theta_i)\cos(\alpha_i) & \sin(\theta_i)\sin(\alpha_i) & a_i\cos(\theta_i) \\ \sin(\theta_i) & \cos(\theta_i)\cos(\alpha_i) & -\cos(\theta_i)\sin(\alpha_i) & a_i\sin(\theta_i) \\ 0 & \sin(\alpha_i) & \cos(\alpha_i) & d_i \\ 0 & 0 & 0 & 1 \end{bmatrix} \quad (1)$$

350 where  $T$  is the manipulator end-effector's Cartesian coordinate;  $d_i$ ,  $\theta_i$ ,  $a_i$ , and  $\alpha_i$  are  
351 associated with each joint's reference frame system.

352 In construction sites, motion planning methods can help the robotic manipulator  
353 autonomously and safely manoeuvre around assembled parts. Based on the kinematic equation  
354 ( $T$ ) derived, a motion planning algorithm was applied. Considering the trade-off between  
355 computational time and path quality, the authors used a redefined sampling-based motion  
356 planning algorithm—Rapidly Exploring Random Tree Star (RRT\*) [41].

357 Given  $\chi$  as the 3-dimensional configuration space for our motion planning problem and  
358  $\chi_{obs}$  as the known obstacle space, the collision-free space can be calculated by  
359  $\chi_{free} = \chi \setminus \chi_{obs}$ . The start state  $x_{start}$  (i.e., the pick-up coordinate), the goal state  $x_{goal}$   
360 (i.e., the assembly coordinate), the 3-dimensional configuration space  $\chi$  and the known  
361 obstacle space  $\chi_{obs}$  are required as inputs in this algorithm.

362 The detailed process of the RRT\* algorithm is presented in Algorithm 2 and explained  
363 below:

---

**Algorithm 2:** Rapidly Exploring Random Tree Star (RRT\*) ( $\chi$ ,  $\chi_{obs}$ ,  $x_{start}$ ,  $x_{goal}$ ,  $N$ )

---

$V \leftarrow x_{start}, x_{goal};$

$E \leftarrow \emptyset;$

for  $i = 1, 2, \dots, N$  do

$x_{rand} \leftarrow \text{Sample}(\chi_{free}, N);$

$x_{nearest} \leftarrow \text{Nearest}(V, x_{rand});$

```

 $x_{new} \leftarrow \text{Steer}(x_{nearest}, x_{rand}, d_{step});$ 
if CollisionFree( $x_{nearest}, x_{new}, \chi_{obs}$ ) then
     $X_{near} \leftarrow \text{Near}(V, x_{new}, r);$ 
     $\eta \leftarrow \text{Line}(x_{nearest}, x_{new}, S);$ 
     $(x_{min}, x_{new}) \leftarrow \text{Parent}(x_{new}, X_{near}, \eta);$ 
     $V \leftarrow V \cup \{x_{new}\};$ 
     $E \leftarrow E \cup \{(x_{min}, x_{new})\};$ 
     $G \leftarrow \text{Rewire}(G, X_{near}, x_{new});$ 
end
end
return  $G(V, E);$ 


```

---

- 364 ● First, the function  $\text{Sample}(\chi_{free})$  generates a random state  $x_{rand}$  inside the collision-
- 365 free space  $\chi_{free}$  based on a uniform distribution. Specifically, a uniform distribution
- 366 means that the probability of the potential position of  $x_{rand}$  at any point within  $\chi_{free}$
- 367 is equal;
- 368 ● Second, a comparison between the randomly sampled state  $x_{rand}$  and the rest states in
- 369 the set of nodes  $V$  is performed to find the nearest state  $x_{nearest}$  to  $x_{rand}$ ;
- 370 ● Third, the function  $\text{Steer}(x_{nearest}, x_{rand}, d_{step})$  generates a new state  $x_{new}$  that is
- 371 closer to  $x_{nearest}$  by connecting  $x_{rand}$  and  $x_{nearest}$  with a steering function;
- 372 ● Fourth, the function  $\text{CollisionFree}(x_{nearest}, x_{new}, \chi_{obs})$  checks if there is any collision
- 373 between the straight path from  $x_{new}$  to  $x_{nearest}$  and the known obstacle space  $\chi_{obs}$ ;
- 374 ● Fifth, if there is no collision found, the function  $\text{Near}(V, x_{new}, r)$  collects a set of states,
- 375 which locates within a spherical space that uses  $x_{new}$  as the centre and a predefined
- 376 parameter  $r$  as the radius;
- 377 ● Sixth, the function  $\text{Line}(x_{nearest}, x_{new}, S)$  connects  $x_{new}$  and  $x_{nearest}$  with a
- 378 straight line. The length of the straight line is equal to another predefined parameter step
- 379 size  $S$ ;
- 380 ● Seventh, the function  $\text{Parent}(x_{new}, X_{near}, \eta)$  selects the state with the minimum cost-
- 381 to-go  $c_{min}$  from the set  $X_{near}$  as the parent state  $x_{min}$ ;

- 382 ● Eighth, the new state  $x_{new}$  is added to the set of nodes  $V$ , and the new edges that connect  
383  $x_{min}$  and  $x_{new}$  is added to the set of edges  $E$ ;
- 384 ● Ninth, the function  $Rewire(G, X_{near}, x_{new})$  keeps adding or removing some edges  
385 between  $x_{new}$  and the states in  $X_{near}$  to ensure the path is optimised and has a  
386 minimum cost;
- 387 ● Last, this algorithm computes the global graph  $G(V, E)$ , where the optimised global path  
388  $\theta = [x_1, \dots x_N]$  is embedded within this global graph after repeating N times.

389 Overall, RRT\* keeps sampling random nodes  $x_{rand}$  within the collision-free space  
390  $\mathcal{X}_{free}$ , and then reviews the global graph  $G(V, E)$  through measuring the potential cost-to-go  
391 to every node  $x \in V$ , which locates within the spherical space near the newly sampling node  
392  $x_{new}$ . An example of applying RRT\* to perform motion planning for a robotic manipulator to  
393 assemble the main beam (short edge) is illustrated in Figure 12. Figures 10a and 10b show a  
394 simulated construction environment, where the two robotic manipulators are simultaneously  
395 assembling the main beams (short edge). In Figure 12a, the end-tip of the manipulators are at  
396 their start points to pick up the prefabricated beams from the trolleys. In Figure 12b, the end-  
397 tip of the manipulators are at their goal points to place the prefabricated beams at the designated  
398 location. Figures 10c and 10d show the corresponding motion planning problem solved by  
399 RRT\* in ROS Rviz. As can be seen, the start point is represented in green, the goal point is  
400 represented in red, the obstacle space is represented in grey, tree branches of the RRT\*  
401 algorithm are represented in orange, and the resulting optimised assembly path is represented  
402 in blue. Note that each manipulator's base coordinate system is marked as a world coordinate  
403 system, and the prefabricated components' assembly coordinates as determined via the task  
404 planning algorithm are unified into the manipulator's base coordinate system for motion  
405 planning.



**Figure 12.** Using robotic manipulators to perform an assembly task in a simulated construction site: (a) and (b) show a simulated construction environment, where the two robotic manipulators are simultaneously assembling the main beams (short edge); (c) and (d) show the corresponding motion planning problem solved by RRT\* in ROS Rviz.

## 7. Testing of the prototype

Tests were performed to evaluate the developed prototype in terms of 1) reasonableness of assembly sequence determined for a given flatpack house BIM model, 2) reachability for the assembly coordinates of prefabricated components, and 3) capability to avoid obstacles.

### 7.1 Reasonableness of assembly sequence

The authors recreated the standard flatpack house unit in Autodesk Revit, and applied the ACASD algorithm of the prototype to locate prefabricated components in the Revit model's reference frame and determine the assembly coordinates and sequence for each component. The result is provided in Table 3 below. As can be seen, the ACASD algorithm can create a reasonable assembly sequence for the flatpack house. First, the frame is assembled (components 1-44, Table 3), and then the wall panels are enclosed (components 45-62, Table 3). The frame

425 consists of bottom and top frames as the transverse bearing constitution and columns as vertical  
 426 supporting, where the sequence implies a bottom-to-top, left-to-right, and back-to-front  
 427 assembly logic. This is reflected in Table 3: components 1-20 for the bottom frame, components  
 428 21-24 for the column, and components 25-44 for the top frame.

429 **Table 3.** Assembly sequence and coordinates of the prefabricated building components.

Sequence	Components	Coordinates	Sequence	Components	Coordinates
1	Beam (Short Edge)	(1.50, 0.00, 0.00)	32	Purlin	(1.50, 2.40, 2.61)
2	Beam (Long Edge)	(0.00, 3.00, 0.00)	33	Purlin	(1.50, 3.00, 2.61)
3	Beam (Long Edge)	(3.00, 3.00, 0.00)	34	Purlin	(1.50, 3.60, 2.61)
4	Beam (Short Edge)	(1.50, 6.00, 0.00)	35	Purlin	(1.50, 4.20, 2.61)
5	Purlin	(1.50, 0.60, 0.01)	36	Purlin	(1.50, 4.80, 2.61)
6	Purlin	(1.50, 1.20, 0.01)	37	Purlin	(1.50, 5.40, 2.61)
7	Purlin	(1.50, 1.80, 0.01)	38	Roof Panel	(1.50, 0.05, 2.66)
8	Purlin	(1.50, 2.40, 0.01)	39	Roof Panel	(1.50, 0.70, 2.66)
9	Purlin	(1.50, 3.00, 0.01)	40	Roof Panel	(1.50, 1.85, 2.66)
10	Purlin	(1.50, 3.60, 0.01)	41	Roof Panel	(1.50, 3.00, 2.66)
11	Purlin	(1.50, 4.20, 0.01)	42	Roof Panel	(1.50, 4.15, 2.66)
12	Purlin	(1.50, 4.80, 0.01)	43	Roof Panel	(1.50, 5.30, 2.66)
13	Purlin	(1.50, 5.40, 0.01)	44	Roof Panel	(1.50, 5.95, 2.66)
14	Floor Panel	(1.50, 0.05, 0.06)	45	Wall Panel	(1.80, -0.06, 1.17)
15	Floor Panel	(1.50, 0.70, 0.06)	46	Wall Panel	(1.83, 6.05, 1.17)
16	Floor Panel	(1.50, 1.85, 0.06)	47	Wall Panel	(2.65, -0.06, 1.30)
17	Floor Panel	(1.50, 3.00, 0.06)	48	Wall Panel	(3.05, 0.65, 1.30)
18	Floor Panel	(1.50, 4.15, 0.06)	49	Wall Panel	(-0.05, 0.66, 1.30)
19	Floor Panel	(1.50, 5.30, 0.06)	50	Wall Panel	(3.05, 1.80, 1.30)
20	Floor Panel	(1.50, 5.95, 0.06)	51	Wall Panel	(-0.05, 1.81, 1.30)
21	Column	(-0.03, -0.03, 1.30)	52	Wall Panel	(3.05, 2.95, 1.30)
22	Column	(3.03, -0.03, 1.30)	53	Wall Panel	(-0.05, 2.96, 1.30)
23	Column	(-0.03, 6.03, 1.30)	54	Wall Panel	(3.05, 4.10, 1.30)
24	Column	(3.03, 6.03, 1.30)	55	Wall Panel	(-0.05, 4.11, 1.30)
25	Beam (Short Edge)	(1.50, 0.00, 2.60)	56	Wall Panel	(3.05, 5.25, 1.30)
26	Beam (Long Edge)	(0.00, 3.00, 2.60)	57	Wall Panel	(-0.05, 5.26, 1.30)
27	Beam (Long Edge)	(3.00, 3.00, 2.60)	58	Wall Panel	(3.05, 5.87, 1.30)
28	Beam (Short Edge)	(1.50, 6.00, 2.60)	59	Wall Panel	(-0.05, 5.88, 1.30)
29	Purlin	(1.50, 0.60, 2.61)	60	Wall Panel	(0.66, 6.05, 1.30)
30	Purlin	(1.50, 1.20, 2.61)	61	Wall Panel	(2.65, 6.05, 1.30)
31	Purlin	(1.50, 1.80, 2.61)	62	Wall Panel	(0.60, -0.06, 1.73)



430 7.2 Reachability for the assembly coordinates

431 The robotic manipulator used in this research is composed of one prismatic joint and six  
432 revolute joints (Figure 11). The relationship between the manipulator joint coordinates and the  
433 end-effector's Cartesian coordinate is given by the kinematic equation ( $T$ ) (1) as derived above.  
434 Thus, the problem of whether a given assembly coordinate is kinematically reachable for the  
435 robotic manipulator can be solved by formulating the following equation:

$$436 \begin{bmatrix} d_1 \\ \theta_2 \\ \theta_3 \\ \theta_4 \\ \theta_5 \\ \theta_6 \\ \theta_7 \end{bmatrix} = T^{-1} \begin{bmatrix} x \\ y \\ z \end{bmatrix} \quad (2)$$


437 where ( $d_1, \theta_2, \theta_3, \theta_4, \theta_5, \theta_6, \theta_7$ ) are the manipulator joint variables, which are subject to  
438 the following motion constraints as mentioned in section 4:  $0 \leq d_1 \leq 8.500 \text{ m}$ ;  $-3.227 \leq$   
439  $\theta_2 \leq 3.227 \text{ rad}$ ;  $-1.483 \leq \theta_3 \leq 0.872 \text{ rad}$ ;  $-1.361 \leq \theta_4 \leq 2.093 \text{ rad}$ ;  $-6.106 \leq \theta_5 \leq$   
440  $6.106 \text{ rad}$ ;  $-2.181 \leq \theta_6 \leq 2.181 \text{ rad}$ ;  $-6.106 \leq \theta_7 \leq 6.106 \text{ rad}$  ;  $T^{-1}$  is the inverse  
441 operation of the kinematic equation ( $T$ ) (1); ( $x, y, z$ ) is a given assembly coordinate. Note that  
442 the assembly coordinates as determined via the task planning algorithm are the geometric  
443 centroids of the prefabricated components. The Cartesian coordinate of the manipulator end-  
444 effector represents the position where a component is adsorbed by the vacuum gripper. To  
445 provide the appropriate ( $x, y, z$ ) input for equation (2), the assembly coordinates are converted  
446 to the Cartesian coordinate of the manipulator end-effector based on the geometric features of  
447 the prefabricated components.

448 Equation (2) is to find a set of ( $d_1, \theta_2, \theta_3, \theta_4, \theta_5, \theta_6, \theta_7$ ) which satisfies a given  
449 assembly coordinate ( $x, y, z$ ). If a solution can be found, the coordinate ( $x, y, z$ ) is reachable  
450 for the manipulator. The 62 assembly coordinates in Table 3 were tested given equation (2) and  
451 the motion range of each joint. The results indicated that using dual robotic manipulators KUKA  
452 KR 120 R3100 (see Figure 5b) enlarges the workspace and can fully cover the spatial extent of  
453 the flatpack house for assembly, where solutions exist for the 62 assembly coordinates. Figure  
454 13 showcases eight examples of assembly coordinates reached by robotic manipulators in a  
455 simulated construction environment. The corresponding solutions for Figure 13 examples are


456 provided in Table 4.




457  
458 (a)




(b)




459  
460 (c)




(d)




461  
462 (e)



(f)



463  
464 (g)



(h)

465 **Figure 13.** Examples of assembly coordinates reached by robotic manipulators in a simulated


466 construction environment: (a) bottom frame main beam (short edge); (b) bottom frame floor  
 467 panel; (c) column; (d) top frame main beam (long edge); (e) top frame purlin; (f) top frame roof  
 468 panel; (g) wall panel (long edge); (h) wall panel (short edge).

469 **Table 4.** Corresponding solutions for Figure 13 examples.

<b>Solution</b>	<b><math>d_1</math> (m)</b>	<b><math>\theta_2</math> (rad)</b>	<b><math>\theta_3</math> (rad)</b>	<b><math>\theta_4</math> (rad)</b>	<b><math>\theta_5</math> (rad)</b>	<b><math>\theta_6</math> (rad)</b>	<b><math>\theta_7</math> (rad)</b>
Figure 13a	0.909	0.000	-1.483	0.371	-1.600	1.234	-2.700
Figure 13b	1.950	0.000	-1.483	0.705	0.000	0.763	0.000
Figure 13c	6.239	0.572	-0.862	0.183	-1.954	-2.006	0.765
Figure 13d	4.318	0.010	-0.028	-0.013	0.232	-0.043	0.232
Figure 13e	2.000	-0.174	-1.232	1.907	-1.681	1.706	-0.889
Figure 13f	1.999	0.000	-0.499	0.785	0.000	1.857	0.000
Figure 13g	3.455	-0.671	-0.754	-0.113	0.805	-1.040	0.485
Figure 13h	0.922	0.000	-1.483	1.174	4.674	1.128	4.394

470 7.3 Capability to avoid obstacles


471 Testing the developed prototype in the simulated construction environment also finds that it has  
 472 satisfactory obstacle avoidance performance. The motion planning RRT\* algorithm  
 473 successfully recognised the robotic manipulator and already-in-place prefabricated components  
 474 as obstacles and generated a series of optimised robotic motions to avoid the obstacles. Figure  
 475 14 presents an example of robotic motion optimisation for top frame purlin assembly. The  
 476 optimisation routine as illustrated sequentially in the sub-figures is interpreted in the figure  
 477 caption.






480  
481

(c)




(d)



482  
483

(e)




(f)



484  
485

(g)



(h)



486  
487

(i)



(j)

488 **Figure 14.** An example of robotic motion optimisation for top frame purlin assembly: (a) and  
489 (b) show that the robotic manipulator hoists vertically the purlin and moves forward along joint  
490 1 axis while having its joint 3 rotate backward and joint 4 rotate forward to keep the end-tip (as

491 well as the purlin) in a distance from the obstacle (i.e., already-in-place flatpack house unit);  
492 (c), (d), (e), (f), and (g) show that joints 3, 4, 5, 6, and 7 of the manipulator adjust their respective  
493 angles cooperatively to achieve the pose in (h) and in the meantime avoid the purlin-obstacle  
494 collision; (h) and (i) show that the robotic manipulator hoists horizontally the purlin and moves  
495 forward along joint 1 axis to approach beneath the assembly coordinate of the purlin; (j) shows  
496 that joints 4, 5, 6, and 7 of the manipulator adjust their respective angles cooperatively to place  
497 the purlin at the designated assembly coordinate.

## 498 **8. Discussion**

499 In scrutinising the scientific question as proposed, the findings suggest that the question has  
500 been answered in this research. The robotic prototype was developed to reflect the construction  
501 characteristics and difficulties of COVID-19 hospitalisation facilities, which consists of a task  
502 planning algorithm and a motion planning algorithm that can respectively: 1) derive a vector  
503 that can determine the mathematical relationship between coordinates of prefabricated  
504 components and assembly sequence, with the consideration of geometry and centroid, for  
505 robotic construction; and 2) analyse the determined assembly sequence and generate robots'  
506 kinematic parameters for performing the assembly of COVID-19 hospitalisation facilities  
507 autonomously without human intervention.

508 As presented in section 7, the developed prototype was tested in three aspects: 1)  
509 determination of the assembly sequence, 2) reachability for the assembly coordinates of  
510 prefabricated components, and 3) capability to avoid obstacles. To quantitatively evaluate the  
511 assembly sequence determination performance, the coordinates of each building component in  
512 the sorted sequence list (Table 3) were scrutinised (section 7.1). As can be seen, the coordinates  
513 were arranged in ascending order along the z-axis (from the bottommost to the topmost), the y-  
514 axis (from the leftmost to the rightmost), then the x-axis (from the rearmost to the foremost).  
515 This implies a reasonable bottom-to-top, left-to-right, and back-to-front assembly logic. To  
516 quantitatively evaluate whether the assembly coordinates of each component are reachable, the  
517 kinematic analysis on the robotic platform was performed (section 7.2). The results showed that  
518 the robot joint solution ( $d_1, \theta_2, \theta_3, \theta_4, \theta_5, \theta_6, \theta_7$ ) existed for all the assembly coordinates  
519 of the 62 prefabricated components. The authors further ran simulations to test whether the joint


520 solutions produce weird robot poses. The results indicated that the robot configurations for all  
521 the assembly coordinates were reasonable and no weird poses were observed. Eight showcase  
522 examples are provided in Figure 13. In addition, the collision avoidance capability of the  
523 developed prototype was tested (section 7.3). The motion planning RRT\* algorithm  
524 successfully recognised the robotic manipulator and already-in-place prefabricated components  
525 as obstacles and generated a series of optimised robotic motions to avoid the obstacles (see an  
526 example presented in Figure 14).

527 The original innovation of this research is to provide the following three outcomes for the  
528 research community:

- 529 1) The Assembly Coordinates and Sequence Determination (ACASD) algorithm (open source:  
530 <https://github.com/yifanrepo/ACASD>). In the existing studies [8–11], the assembly  
531 coordinates of prefabricated building components were predetermined for the robotic  
532 assembly. However, the function of determining the assembly sequence of the prefabricated  
533 building components was not considered in their approaches. The ACASD algorithm can  
534 be used to determine both the assembly coordinates and sequence for a given flatpack house  
535 BIM model.
- 536 2) The seven degree-of-freedom (DOF) robotic manipulator kinematic equation. The robotic  
537 manipulators used in the previous studies [8–11] in this field only have six revolute joints  
538 (i.e., six DOF) and the bases of their manipulators are fixed. In this research, the  
539 manipulator has an additional prismatic joint based on the six revolute joints (i.e., seven  
540 DOF), which enables the base of the manipulator to move along a linear track to attain a  
541 higher range of workspace. The seven DOF equation developed in this research  
542 incorporates the manipulator base’s moving capability in the kinematic design, which is  
543 more suitable for construction-related scenarios.
- 544 3) The virtual environment for simulating the assembly of flatpack house using robotic  
545 manipulators (open source: <https://github.com/yifanrepo/virtual-construction>). The authors  
546 rigorously modelled the environment to reflect physical effects (e.g., gravity) and  
547 workplace resources (e.g., machinery, prefabricated building components, and workers).

548 In a real project, the robotic prototype developed in this research can be set up as the digital

549 representation of the project and uses its self-contained task and motion planning algorithms to  
550 generate useful data input for instructing the robotic assembly. Once the robotic manipulators  
551 are set up in the real world, the ROS environment of the prototype can be used to recreate the  
552 project's real-world situations (Figure 15). This is enabled by using 3D modelling to create  
553 digital companions for the on-site physical objects, which provides a way to project the  
554 workplace settings into the prototype's digital world. Therefore, the digital environment forms  
555 a one-to-one correspondence mapping of the physical objects' shape, texture, location, and  
556 motion (see Figure 15). This ensures that the properties of the physical objects can be well  
557 transferred to their digital counterparts and the virtual representation of the workplace is  
558 efficient for spatial reasoning and motion planning. Specifically, the workflow of our prototype  
559 is as follows. First, the ROS terminal receives the assembly sequence and coordinates data from  
560 BIM, and marks the pick-up and assembly locations of the prefabricated building components  
561 in its spatial reference system (see Figure 15). The pick-up and assembly locations represent  
562 the start and goal states for motion planning respectively. Then, the RRT\* algorithm generates  
563 the manipulators' joint parameters for performing the assembly of the flatpack house based on  
564 the marked start and goal states in the ROS environment, and publishes joint control signals to  
565 the digital processors of the robotic manipulators in the real world. In this situation, the end-  
566 tips of the manipulators will be driven by the signals to pick up the prefabricated components  
567 from the trolleys and follow a pre-determined sequence to transfer each component to the  
568 assembly coordinates (see Figure 15). Note that as electrical outlets are not always available in  
569 the exact location where the manipulators are positioned on-site, extension cords can be used  
570 to reach the manipulators' locations and supply the necessary power to get the assembly job  
571 done. When the assembly of a flatpack house unit completes, a mobile crane is used to lift the  
572 unit from the assembling area and install the unit into the hoisting area (see Figure 15).



573

574 **Figure 15.** The robotic platform for constructing prefabricated hospitalisation facilities.

575 The practical value of our robotic prototype is twofold:

- 576 1) Once the robotic manipulators are set up in a real project, the prototype can publish useful  
 577 joint control signals to the digital processors of the manipulators for the assembly of  
 578 COVID-19 hospitalisation facilities.
- 579 2) In a real project, the robotic manipulators can replace human labour in the assembly of  
 580 flatpack house, where one worker is needed to operate the data transmission inside the  
 581 robotic prototype. In this case, the number of workers required in the construction  
 582 procedure can be significantly reduced compared with the traditional method, which  
 583 contributes to the mitigation of COVID-19 spread on construction sites.

584 The authors acknowledge that although our prototype was tested in a ROS environment  
 585 rather than the actual implementation, the environment was rigorously modelled to provide a  
 586 convincing experimental condition. First, great care was taken to make the physical properties  
 587 of the environment as close to that of the real world, which consisted of density, gravity,  
 588 damping, dimension, and material colour and texture. Second, in a real project, the on-site  
 589 construction resources can be set up in one-to-one correspondence with the settings in the ROS  
 590 environment (see Figure 15) (e.g., the number and pick-up locations of the prefabricated  
 591 building components). This ensures that the properties of the digital objects in ROS can be well



592 transferred to their physical counterparts in the real world and the virtual representation of the  
 593 workplace is efficient for spatial reasoning and motion planning. Third, the environment  
 594 included an accurate kinematic representation of the robot so that the planned motions as  
 595 verified in the environment can be well transferred to the reality for assembling prefabricated  
 596 hospitalisation facilities. The authors carried out a pilot trial in the lab to investigate whether  
 597 the verified robot motions are achievable in the real world. The results showed that the joint  
 598 motions and end-tip outreaches as planned and verified for the robot in ROS could be achieved  
 599 in the reality. Figure 16 shows an example of reaching a predetermined end-tip coordinate for  
 600 assembling the purlin component in the lab setting. As can be seen, the end-tip coordinate is  
 601 (1.400, 0.300, 1.100) in the manipulator's base coordinate system, which could be achieved  
 602 with joint parameters (1.400 m, -0.671 rad, -0.824 rad, 1.013 rad, 0.625 rad, -1.040 rad, 0.485  
 603 rad).



end-tip coordinate	
(1.400, 0.300, 1.100)	

joint	parameter
joint 1	1.400 m
joint 2	-0.671 rad
joint 3	-0.824 rad
joint 4	1.013 rad
joint 5	0.625 rad
joint 6	-1.040 rad
joint 7	0.485 rad

604

605

**Figure 16.** Pilot trial in the lab.

## 606 **9. Conclusion and future work**

607 This research presents a BIM-based prototype for robotic assembly of the standard unit of  
 608 COVID-19 hospitalisation facilities—flatpack house—with prefabricated components. The  
 609 development of the prototype consisted of a task planning algorithm and a motion planning  
 610 algorithm. The task planning algorithm—Assembly Coordinates and Sequence Determination  
 611 (ACASD)—is designed to utilise the spatial information contained in a BIM model to locate

612 the assembly coordinates for the prefabricated components. Then the ACASD algorithm  
613 determines the assembly sequence by following a bottom-to-top, left-to-right, and back-to-front  
614 logic according to the relative positions of the prefabricated components in the BIM model.  
615 The motion planning algorithm—Rapidly Exploring Random Tree Star (RRT\*)—incorporates  
616 the manipulator base’s moving capability in the kinematic analysis, and regards the manipulator  
617 and already-in-place prefabricated components as obstacles to generate a series of optimised  
618 robotic motions.

619 Different types of tests were performed to assess the developed prototype and the  
620 corresponding results demonstrated that the prototype has satisfactory performance in all the  
621 tests. First, the prototype can create a reasonable assembly sequence for the flatpack house.  
622 Second, using dual robotic manipulators KUKA KR 120 R3100 enlarges the workspace and  
623 can fully cover the spatial extent of the flatpack house unit for assembly, where the assembly  
624 coordinates of the 62 prefabricated components are kinematically reachable. Third, the motion  
625 planning algorithm successfully recognised the robotic manipulator and already-in-place  
626 prefabricated components as obstacles and generated a series of optimised robotic motions to  
627 avoid the obstacles.

628 Overall, this research highlights the significance of using robotic technologies to deliver  
629 construction projects under pandemic circumstances, and provides a prototype that can be used  
630 to generate reasonable task and motion planning for robotic assembly of COVID-19  
631 hospitalisation units—flatpack house. Meanwhile, it is potentially useful for other emergency  
632 cases that utilise the flatpack house as the standard unit (e.g., earthquake, deluge), which further  
633 extends the generalisability of the research outcome. On the other hand, the present research  
634 contributed to the existing literature in addition to the mentioned practical implications. More  
635 specifically, the developed prototype fills in the following knowledge gaps: 1) determining the  
636 assembly sequence of building components, and 2) generating robots’ kinematic parameters for  
637 performing the assembly of COVID-19 hospitalisation facilities, while incorporating the robot  
638 base's moving capability in the kinematic design to attain a reasonable range of workspace.

639 However, this research has the following limitation and subsequent research needs to be  
640 conducted shortly. This research aimed at the assembly steps of determining the coordinates

641 and sequence for the prefabricated components, and using robotic manipulators to place the  
642 components at the designated location in the designated order. There is a further auxiliary  
643 procedure involved, which is to bolt the prefabricated components. This paper is a part of an  
644 ongoing research project. In the subsequent research, the authors will investigate further the use  
645 of a collaborative robot (e.g., aerial operation robot) to assist in screwing bolt connections after  
646 the components are placed at the designated locations.

#### 647 **Acknowledgement**

648 This work was partially supported by China's National Natural Science Foundation under Grant  
649 No. (52108179).

#### 650 **References**

- 651 [1] A.M. Anter, D. Oliva, A. Thakare, Z. Zhang, AFCM-LSMA: New intelligent model  
652 based on Lévy slime mould algorithm and adaptive fuzzy C-means for identification of  
653 COVID-19 infection from chest X-ray images, *Advanced Engineering Informatics*. 49  
654 (2021) 101317. <https://doi.org/10.1016/j.aei.2021.101317>.
- 655 [2] H. Luo, J. Liu, C. Li, K. Chen, M. Zhang, Ultra-rapid delivery of specialty field hospitals  
656 to combat COVID-19: Lessons learned from the Leishenshan Hospital project in Wuhan,  
657 *Automation in Construction*. 119 (2020) 103345.  
658 <https://doi.org/10.1016/j.autcon.2020.103345>.
- 659 [3] L.-K. Chen, R.-P. Yuan, X.-J. Ji, X.-Y. Lu, J. Xiao, J.-B. Tao, X. Kang, X. Li, Z.-H. He,  
660 S. Quan, L.-Z. Jiang, Modular composite building in urgent emergency engineering  
661 projects: A case study of accelerated design and construction of Wuhan Thunder God  
662 Mountain/Leishenshan hospital to COVID-19 pandemic, *Automation in Construction*.  
663 124 (2021) 103555. <https://doi.org/10.1016/j.autcon.2021.103555>.
- 664 [4] V. Bushell, L. Thomas, J. Combes, Inside The O2: the NHS Nightingale Hospital  
665 London education center, *Journal of Interprofessional Care*. 34 (2020) pp.698-701.  
666 <https://doi.org/10.1080/13561820.2020.1823949>.
- 667 [5] R. Alizadehsani, Z. Alizadeh Sani, M. Behjati, Z. Roshanzamir, S. Hussain, N. Abedini,  
668 F. Hasanzadeh, A. Khosravi, A. Shoeibi, M. Roshanzamir, P. Moradnejad, S. Nahavandi,

- 669 F. Khozeimeh, A. Zare, M. Panahiazar, U.R. Acharya, S.M.S. Islam, Risk factors  
670 prediction, clinical outcomes, and mortality in COVID-19 patients, *Journal of Medical*  
671 *Virology*. 93 (2021) pp.2307-2320. <https://doi.org/10.1002/jmv.26699>.
- 672 [6] A. Alsharif, S. Banerjee, S.M. Uddin, A. Albert, E. Jaselskis, Early Impacts of the  
673 COVID-19 Pandemic on the United States Construction Industry, *International Journal*  
674 *of Environmental Research and Public Health*. 18 (2021) 1559.  
675 <https://doi.org/10.3390/ijerph18041559>.
- 676 [7] K. Simonson, Construction Data, The Associated General Contractors of America.  
677 (2021). <https://www.agc.org/learn/construction-data> (accessed August 21, 2021).
- 678 [8] Y. Terada, S. Murata, Automatic Modular Assembly System and its Distributed Control,  
679 *The International Journal of Robotics Research*. 27 (2008) pp.445-462.  
680 <https://doi.org/10.1177/0278364907085562>.
- 681 [9] J. Willmann, M. Knauss, T. Bonwetsch, A.A. Apolinarska, F. Gramazio, M. Kohler,  
682 Robotic timber construction — Expanding additive fabrication to new dimensions,  
683 *Automation in Construction*. 61 (2016) pp.16-23.  
684 <https://doi.org/10.1016/j.autcon.2015.09.011>.
- 685 [10] L. Ding, W. Jiang, Y. Zhou, C. Zhou, S. Liu, BIM-based task-level planning for robotic  
686 brick assembly through image-based 3D modeling, *Advanced Engineering Informatics*.  
687 43 (2020) 100993. <https://doi.org/10.1016/j.aei.2019.100993>.
- 688 [11] N. King, M. Bechthold, A. Kane, P. Michalatos, Robotic tile placement: Tools,  
689 techniques and feasibility, *Automation in Construction*. 39 (2014) pp.161-166.  
690 <https://doi.org/10.1016/j.autcon.2013.08.014>.
- 691 [12] J.M. Davila Delgado, L. Oyedele, A. Ajayi, L. Akanbi, O. Akinade, M. Bilal, H.  
692 Owolabi, Robotics and automated systems in construction: Understanding industry-  
693 specific challenges for adoption, *Journal of Building Engineering*. 26 (2019) 100868.  
694 <https://doi.org/10.1016/j.jobbe.2019.100868>.
- 695 [13] J. Czarnowski, A. Dąbrowski, M. Maciaś, J. Główska, J. Wrona, Technology gaps in  
696 Human-Machine Interfaces for autonomous construction robots, *Automation in*  
697 *Construction*. 94 (2018) pp.179-190. <https://doi.org/10.1016/j.autcon.2018.06.014>.

- 698 [14] S. Cai, Z. Ma, M.J. Skibniewski, S. Bao, Construction automation and robotics for high-  
699 rise buildings over the past decades: A comprehensive review, *Advanced Engineering*  
700 *Informatics*. 42 (2019) 100989. <https://doi.org/10.1016/j.aei.2019.100989>.
- 701 [15] H. Ardiny, S. Witwicki, F. Mondada, Construction automation with autonomous mobile  
702 robots: A review, in: 2015 3rd RSI International Conference on Robotics and  
703 Mechatronics (ICROM), 2015: pp. 418–424.  
704 <https://doi.org/10.1109/ICRoM.2015.7367821>.
- 705 [16] Q. Chen, B. García de Soto, B.T. Adey, Construction automation: Research areas,  
706 industry concerns and suggestions for advancement, *Automation in Construction*. 94  
707 (2018) pp.22-38. <https://doi.org/10.1016/j.autcon.2018.05.028>.
- 708 [17] K. Jung, B. Chu, D. Hong, Robot-based construction automation: An application to steel  
709 beam assembly (Part II), *Automation in Construction*. 32 (2013) pp.62-79.  
710 <https://doi.org/10.1016/j.autcon.2012.12.011>.
- 711 [18] O. Davtalab, A. Kazemian, B. Khoshnevis, Perspectives on a BIM-integrated software  
712 platform for robotic construction through Contour Crafting, *Automation in Construction*.  
713 89 (2018) pp.13-23. <https://doi.org/10.1016/j.autcon.2018.01.006>.
- 714 [19] O. Kontovourkis, G. Tryfonos, C. Georgiou, Robotic additive manufacturing (RAM)  
715 with clay using topology optimization principles for toolpath planning: the example of  
716 a building element, *Architectural Science Review*. 63 (2020) pp.105-118.  
717 <https://doi.org/10.1080/00038628.2019.1620170>.
- 718 [20] M. Taghavi, H. Heredia, K. Iturralde, H. Halvorsen, T. Bock, Development of a Modular  
719 End Effector for the installation of Curtain Walls with cable-robots, *Journal of Facade*  
720 *Design and Engineering*. 6 (2018) pp.1-8. <https://doi.org/10.7480/jfde.2018.2.2067>.
- 721 [21] P. Martinez, R. Ahmad, M. Al-Hussein, A vision-based system for pre-inspection of  
722 steel frame manufacturing, *Automation in Construction*. 97 (2019) pp.151-163.  
723 <https://doi.org/10.1016/j.autcon.2018.10.021>.
- 724 [22] N. Malik, R. Ahmad, M. Al-Hussein, Generation of safe tool-paths for automatic  
725 manufacturing of light gauge steel panels in residential construction, *Automation in*  
726 *Construction*. 98 (2019) pp.46-60. <https://doi.org/10.1016/j.autcon.2018.11.023>.

- 727 [23] C. Zhou, B. Tang, L. Ding, P. Sekula, Y. Zhou, Z. Zhang, Design and automated  
728 assembly of Planetary LEGO Brick for lunar in-situ construction, *Automation in*  
729 *Construction*. 118 (2020) 103282. <https://doi.org/10.1016/j.autcon.2020.103282>.
- 730 [24] Y. Yu, H. Guo, Q. Ding, H. Li, M. Skitmore, An experimental study of real-time  
731 identification of construction workers' unsafe behaviors, *Automation in Construction*.  
732 82 (2017) pp.193-206. <https://doi.org/10.1016/j.autcon.2017.05.002>.
- 733 [25] R.J. Scherer, P. Katranuschkov, BIMification: How to create and use BIM for  
734 retrofitting, *Advanced Engineering Informatics*. 38 (2018) pp.54-66.  
735 <https://doi.org/10.1016/j.aei.2018.05.007>.
- 736 [26] B. Tao, X. Zhao, S. Yan, H. Ding, Kinematic modeling and control of mobile robot for  
737 large-scale workpiece machining, *Proceedings of the Institution of Mechanical*  
738 *Engineers, Part B: Journal of Engineering Manufacture*. 236 (2020) pp.29-38.  
739 <https://doi.org/10.1177/0954405420933708>.
- 740 [27] A. Jokić, M. Petrović, Z. Miljković, Semantic segmentation based stereo visual servoing  
741 of nonholonomic mobile robot in intelligent manufacturing environment, *Expert*  
742 *Systems with Applications*. 190 (2022) 116203.  
743 <https://doi.org/https://doi.org/10.1016/j.eswa.2021.116203>.
- 744 [28] U. Izagirre, I. Andonegui, I. Landa-Torres, U. Zurutuza, A practical and synchronized  
745 data acquisition network architecture for industrial robot predictive maintenance in  
746 manufacturing assembly lines, *Robotics and Computer-Integrated Manufacturing*. 74  
747 (2022) 102287. <https://doi.org/https://doi.org/10.1016/j.rcim.2021.102287>.
- 748 [29] Y. Zhang, J. Xiao, Z. Zhang, H. Dong, Intelligent Design of Robotic Welding Process  
749 Parameters Using Learning-Based Methods, *IEEE Access*. 10 (2022) pp.13442-13450.  
750 <https://doi.org/10.1109/ACCESS.2022.3146404>.
- 751 [30] C. Li, P. Zheng, S. Li, Y. Pang, C.K.M. Lee, AR-assisted digital twin-enabled robot  
752 collaborative manufacturing system with human-in-the-loop, *Robotics and Computer-*  
753 *Integrated Manufacturing*. 76 (2022) 102321.  
754 <https://doi.org/https://doi.org/10.1016/j.rcim.2022.102321>.
- 755 [31] F. Tang, T. Ma, J. Zhang, Y. Guan, L. Chen, Integrating three-dimensional road design

- 756 and pavement structure analysis based on BIM, *Automation in Construction*. 113 (2020)  
757 103152. <https://doi.org/10.1016/j.autcon.2020.103152>.
- 758 [32] N. Melenbrink, J. Werfel, A. Menges, On-site autonomous construction robots:  
759 Towards unsupervised building, *Automation in Construction*. 119 (2020) 103312.  
760 <https://doi.org/10.1016/j.autcon.2020.103312>.
- 761 [33] E. Kiraci, A. Palit, M. Donnelly, A. Attridge, M.A. Williams, Comparison of in-line and  
762 off-line measurement systems using a calibrated industry representative artefact for  
763 automotive dimensional inspection, *Measurement*. 163 (2020) 108027.  
764 <https://doi.org/10.1016/j.measurement.2020.108027>.
- 765 [34] M. Nahangi, J. Yeung, C.T. Haas, S. Walbridge, J. West, Automated assembly  
766 discrepancy feedback using 3D imaging and forward kinematics, *Automation in*  
767 *Construction*. 56 (2015) pp.36-46. <https://doi.org/10.1016/j.autcon.2015.04.005>.
- 768 [35] KUKA, KUKA KR 120 R3100, (2021). [https://www.kuka.com/en-](https://www.kuka.com/en-en/products/robotics-systems/industrial-robots/kr-quantec)  
769 [en/products/robotics-systems/industrial-robots/kr-quantec](https://www.kuka.com/en-en/products/robotics-systems/industrial-robots/kr-quantec) (accessed August 21, 2021).
- 770 [36] M. Huang, L. He, D. Choi, J. Pecchia, Y. Li, Picking dynamic analysis for robotic  
771 harvesting of *Agaricus bisporus* mushrooms, *Computers and Electronics in Agriculture*.  
772 185 (2021) 106145. <https://doi.org/10.1016/j.compag.2021.106145>.
- 773 [37] S. Fernández-Rodríguez, J.P. Cortés-Pérez, P.P. Muriel, R. Tormo-Molina, J.M. Maya-  
774 Manzano, Environmental impact assessment of Pinaceae airborne pollen and green  
775 infrastructure using BIM, *Automation in Construction*. 96 (2018) pp.494-507.  
776 <https://doi.org/10.1016/j.autcon.2018.10.011>.
- 777 [38] K. Zhang, Y. Zhu, C. Lou, P. Zheng, M. Kovač, A Design and Fabrication Approach  
778 for Pneumatic Soft Robotic Arms Using 3D Printed Origami Skeletons, in: 2019 2nd  
779 IEEE International Conference on Soft Robotics (RoboSoft), 2019: pp. 821–827.  
780 <https://doi.org/10.1109/ROBOSOFT.2019.8722719>.
- 781 [39] K. Renuka, N. Bhuvanesh, J. Reena Catherine, Kinematic and Dynamic Modelling and  
782 PID Control of Three Degree-of-Freedom Robotic Arm BT, in: G. Kumaresan, N.S.  
783 Shanmugam, V. Dhinakaran (Eds.), *Advances in Materials Research*, Springer  
784 Singapore, Singapore, 2021: pp. 867–882. <https://doi.org/10.1007/978-981-15-8319->

- 785 3\_87.
- 786 [40] M.M. Alam, S. Ibaraki, K. Fukuda, S. Morita, H. Usuki, Identification of a Kinematic  
787 Model of a 6DOF Industrial Manipulator With Angular Positioning Deviation “Error  
788 Map” of Rotary Axes, in: 2020 International Symposium on Flexible Automation,  
789 Online, 2020: pp. 45–49. <https://doi.org/10.1115/ISFA2020-9655>.
- 790 [41] S. Karaman, E. Frazzoli, Sampling-based algorithms for optimal motion planning, The  
791 International Journal of Robotics Research. 30 (2011) pp.846-894.  
792 <https://doi.org/10.1177/0278364911406761>.
- 793